

**Atlantic Coast of Long Island  
Jones Inlet to East Rockaway Inlet  
Long Beach Island, New York  
Coastal Storm Risk Management Project**

**HURRICANE SANDY LIMITED REEVALUATION REPORT**

**Appendix C:  
Cost Engineering**



**U.S. Army Corps of Engineers  
New York District**

**February 2014**

# Appendix C – Cost Engineering

## TABLE OF CONTENTS

### Table of Contents

Introduction.....	3
Table C-1 – Project First Cost.....	5
Table C-2 – Annualized Cost.....	7
Table C-3 – Renourishment Cost .....	8
Table C-4 – Major Rehab Cost .....	9
Table C-5 – Monitoring Cost.....	10
Table C-6 – Cost Apportionment .....	12
Total Project Cost Summary.....	13
Abbreviated Risk Analysis (ARA) Results.....	18
Schedule .....	19
DQC Comments/Responses .....	20

## Introduction

This Appendix presents the detailed cost estimate and pertinent information for the recommended plan in the HSRR dated November 2013. The recommended plan primarily consists of dredging 4,720,000 CY of material from the borrow area approximately 2 miles from the shore, and extensive groin work (both new construction and rehabilitation of existing) along the shoreline, as well as shoreline structures, sand fencing, and dune grass placement. The project is assumed to go out for solicitation as 3 separate contracts:

- Contract 1 will consist of the construction of two new groins, the rehab of 2 existing groins at Point Lookout, rehab of 4 existing groins at Long Beach, and the rehab of the Point Lookout terminal groin.
- Contract 2 will consist of the construction of two new groins and the rehab of 11 existing groins at Long Beach.
- Contract 3 will consist of the dredging/beach fill, shoreline structures, and the dune grass plantings and sand fence.

The costs for the groin construction component of the project were developed by utilizing actual construction data from ongoing and historical jobsites for similar work, as well as soliciting vendor quotes for major material costs, which included each of the stone classes (armor, underlayer, core/bedding stone), steel sheet piling, and geotextile. The material and delivery price for the stone was based on truck-hauling to the site from quarries in central New York with construction utilizing land-based equipment. Equipment rates were updated with the latest MII Region 1 Equipment Book (2011 version), labor rates were updated using Davis-Bacon rates from the project area, and current fuel costs were used from the EIA website.

The beach fill cost was developed using CEDEP with a Generic Large Hopper dredge, with an average production rate of 429,000 cy per month and historical factors, which coincide with the project area. For initial construction, beach fill placement is required to be coordinated with groin construction in order to prevent wasting material placement. If beach fill is placed in the seaward area of the groin before starting groin construction, the material must be excavated out to place the stone once construction progresses that far out. Therefore, full beach sections are to be completed at the groin locations to once the groin construction is finished. The large hopper dredge is assumed to dredge the material, travel to a pump-out location, and pump the sand to shore using a booster pump. There it will be placed and graded by a shore crew consisting of bulldozers and loaders. The total unit price of \$11.70/CY compares well with recent bid data for large hopper jobs in the area. References:

- Long Branch, Seabright to Manasquan Reach 3B, bid date 2 Aug 13. Large hopper, 3.3M CY. IGE price \$11.88/CY, avg bid price \$11.80/CY.
- Seabright, NJ CT Reach 2A, bid date 11 Jun 13. Large Hopper, 2.5M CY. IGE Price \$12.46/CY, avg bid price \$12.35/CY.

The dune grass, sand fence, and shoreline structures cost were developed with production rates obtained from a combination of the 2012 MII cost book, RS Means and pricing from websites and vendor quotes for some of the line items. This work will be completed after the beach fill work has been completed. Table C-1 shows the initial construction costs, or 'project first costs.'

Costs for air mitigation (Clean Air Act) were developed by Environmental based on the tons of air emissions produced by the equipment on site. The equipment list and equipment hours for each piece of equipment in the MII estimate were sent to Environmental so that they could develop a tonnage quantity of air emissions for the whole project. An offset quote from a broker was received by Environmental at a current market price of \$30-40/ton. That is how the \$2M number was developed.

Costs for Cultural Resources were developed based off an ongoing contract at Long Beach for a Phase I investigation for possible shipwrecks. That contract cost is roughly \$180K. If the Phase I investigation turns up a shipwreck, then a Phase II investigation for one wreck would be about \$200K, based on the current NY/NJ Harbor project. This estimate assumes the possibility that 2 wrecks may be discovered.  $\$180\text{K} + \$200\text{K} + \$200\text{K} = \$580\text{K}$ , round up to \$600K.

However, since these are project costs and not construction contract costs, these dollar amounts are assumed to be part of PED costs. Therefore, the \$2.6M in additional costs have been added to the "Planning" PED cost, along with the 1% that was originally budgeted. The two folders originally containing these costs have been removed from the MII estimate.

Annualized costs are based on an economic project life of 50 years and an interest rate of 3-1/2%. The annual charges include the annualized first costs along with periodic nourishment every 5 years, major rehab costs, coastal monitoring, and dune/groin maintenance. These costs are shown in table C-2.

The periodic renourishment volume to be placed at 5-year cycles subsequent to commencement of construction and throughout the 50-year economic life is 1,770,000 CY per cycle. The renourishment beach fill is assumed to be placed in the same manner as the beach fill for the main contracts; with a large hopper dredge pumping the fill onto the shore, and a shore crew placing the material. Annualized renourishment costs are shown in Table C-4.

Major rehabilitation costs are for restoring the design profile due to significant storm events beyond those that were designed for in the renourishment cycle. The threshold at which major rehabilitation costs are incurred is based on the storm event that causes the erosion volume to exceed 15 cy/lf along the beach front. This is the average nourishment volume anticipated to be available at the midpoint of the renourishment cycle because the significant storm event has a 50% chance of occurring earlier or later than the cycle midpoint. Annualized major rehab costs are shown in Table C-5.

Coastal monitoring costs include semi-annual surveys over the 50-year project life and environmental monitoring over the first 5 years of the project. Annualized monitoring costs are shown in Table C-6.

# Table C-1 – Project First Cost

## Long Beach Island, NY

October 2013 Price Level

### Hurricane Sandy Limited Reevaluation Report Cost Estimate Summary

Feat. Acct.	Description	Qty	UoM	Unit Price	Subtotal	Cont. %	Cont \$\$	Total Cost
<b>Contract 1</b>								
01	Lands & Damages	1	LS	\$ 145,010	\$ 145,010	20.00%	\$ 29,002	\$ 174,012
	<b>Total Lands &amp; Damages</b>				<b>\$ 145,010</b>		<b>\$ 29,002</b>	<b>\$ 174,012</b>
10	Breakwater and Seawalls							
	Mobilization & Demobilization	1	LS	\$ 1,630,490	\$ 1,630,490	21.80%	\$ 355,473	\$ 1,985,962
	<b>Groin A Construction</b>							
	Excavation	9,000	BCY	\$ 10.07	\$ 90,599	21.80%	\$ 19,752	\$ 110,351
	Geotextile	8,611	SY	\$ 26.55	\$ 228,649	21.80%	\$ 49,849	\$ 278,498
	Core/Bedding Stone	16,900	TON	\$ 151.69	\$ 2,563,535	21.80%	\$ 558,891	\$ 3,122,426
	Class D Armor Stone	9,900	TON	\$ 191.18	\$ 1,892,653	21.80%	\$ 412,628	\$ 2,305,282
	Class B/C Armor Stone	17,900	TON	\$ 246.23	\$ 4,407,595	21.80%	\$ 960,926	\$ 5,368,521
	<b>Groin B Construction</b>							
	Excavation	9,000	BCY	\$ 12.21	\$ 109,874	21.80%	\$ 23,954	\$ 133,828
	Geotextile	7,278	SY	\$ 26.55	\$ 193,253	21.80%	\$ 42,132	\$ 235,386
	Core/Bedding Stone	12,300	TON	\$ 151.69	\$ 1,865,768	21.80%	\$ 406,767	\$ 2,272,535
	Class D Armor Stone	8,200	TON	\$ 191.18	\$ 1,567,652	21.80%	\$ 341,773	\$ 1,909,425
	Class B/C Armor Stone	14,800	TON	\$ 246.31	\$ 3,645,369	21.80%	\$ 794,748	\$ 4,440,118
	<b>Rehab Existing Groins</b>							
	Class B/C Armor Stone	10,800	TON	\$ 268.98	\$ 2,904,988	21.80%	\$ 633,334	\$ 3,538,322
	<b>Point Lookout Terminal Groin Rehab</b>							
	Steel Sheet Piling	28,772	SF	\$ 66.72	\$ 1,919,730	21.80%	\$ 418,532	\$ 2,338,261
	Excavation	2,600	BCY	\$ 12.21	\$ 31,741	21.80%	\$ 6,920	\$ 38,661
	Geotextile	3,145	SY	\$ 26.55	\$ 83,509	21.80%	\$ 18,206	\$ 101,716
	Core/Bedding Stone	3,906	TON	\$ 206.61	\$ 807,033	21.80%	\$ 175,946	\$ 982,979
	Class D Armor Stone	5,700	TON	\$ 191.18	\$ 1,089,709	21.80%	\$ 237,574	\$ 1,327,283
	Class B/C Armor Stone	13,700	TON	\$ 245.61	\$ 3,364,808	21.80%	\$ 733,582	\$ 4,098,389
	<b>Total Breakwaters &amp; Seawalls</b>				<b>\$ 28,396,957</b>		<b>\$ 6,190,987</b>	<b>\$ 34,587,944</b>
30	Engineering & Design	1	LS	\$ 4,615,000	\$ 4,615,000	14.91%	\$ 687,966	\$ 5,302,966
31	Construction Management	1	LS	\$ 2,172,000	\$ 2,172,000	14.91%	\$ 323,784	\$ 2,495,784
	<b>Total Contract #1</b>				<b>\$ 35,328,967</b>		<b>\$ 7,231,740</b>	<b>\$ 42,560,706</b>
<b>Contract 2</b>								
01	Lands & Damages	1	LS	\$ -	\$ -	20.00%	\$ -	\$ -
	<b>Total Lands &amp; Damages</b>				<b>\$ -</b>		<b>\$ -</b>	<b>\$ -</b>
10	Breakwater and Seawalls							
	Mobilization & Demobilization	1	LS	\$ 1,304,392	\$ 1,304,392	21.80%	\$ 284,378	\$ 1,588,770
	<b>Groin C Construction</b>							
	Excavation	9,000	BCY	\$ 12.21	\$ 109,874	21.80%	\$ 23,954	\$ 133,828
	Geotextile	5,333	SY	\$ 26.55	\$ 141,608	21.80%	\$ 30,873	\$ 172,480
	Core/Bedding Stone	6,600	TON	\$ 151.69	\$ 1,001,144	21.80%	\$ 218,265	\$ 1,219,409
	Class D Armor Stone	3,500	TON	\$ 191.18	\$ 669,120	21.80%	\$ 145,879	\$ 814,999
	Class B/C Armor Stone	7,400	TON	\$ 247.90	\$ 1,834,488	21.80%	\$ 399,947	\$ 2,234,435

# Long Beach Island, NY

October 2013 Price Level

## Hurricane Sandy Limited Reevaluation Report Cost Estimate Summary

Feat. Acct.	Description	Qty	UoM	Unit Price	Subtotal	Cont. %	Cont \$\$	Total Cost
Groin D Construction								
	Excavation	9,000	BCY	\$ 12.21	\$ 109,874	21.80%	\$ 23,954	\$ 133,828
	Geotextile	4,889	SY	\$ 26.55	\$ 129,818	21.80%	\$ 28,302	\$ 158,120
	Core/Bedding Stone	6,100	TON	\$ 151.69	\$ 925,300	21.80%	\$ 201,730	\$ 1,127,030
	Class D Armor Stone	3,200	TON	\$ 191.18	\$ 611,767	21.80%	\$ 133,375	\$ 745,142
	Class B/C Armor Stone	6,800	TON	\$ 247.89	\$ 1,685,662	21.80%	\$ 367,501	\$ 2,053,163
Rehab Existing Groins								
	Class B/C Armor Stone	19,800	TON	\$ 268.98	\$ 5,325,812	21.80%	\$ 1,161,112	\$ 6,486,923
<b>Total Breakwaters &amp; Seawalls</b>					<b>\$ 13,848,857</b>		<b>\$ 3,019,271</b>	<b>\$ 16,868,127</b>
30	Engineering & Design	1	LS	\$ 3,185,237	\$ 3,185,237	14.91%	\$ 474,829	\$ 3,660,066
31	Construction Management	1	LS	\$ 1,149,875	\$ 1,149,875	14.91%	\$ 171,414	\$ 1,321,289
<b>Total Contract #2 (WITHOUT Deferred Groins)</b>					<b>\$ 18,183,968</b>		<b>\$ 3,665,514</b>	<b>\$ 21,849,482</b>
<b>Groins E &amp; F (Deferred)</b>								
	Excavation	18,000	BCY	\$ 12.21	\$ 219,748	21.80%	\$ 47,908	\$ 267,656
	Geotextile	10,667	SY	\$ 26.55	\$ 283,233	21.80%	\$ 61,749	\$ 344,982
	Core/Bedding Stone	13,200	TON	\$ 151.69	\$ 2,002,288	21.80%	\$ 436,531	\$ 2,438,818
	Class D Armor Stone	7,000	TON	\$ 191.18	\$ 1,338,240	21.80%	\$ 291,757	\$ 1,629,997
	Class B/C Armor Stone	14,800	TON	\$ 247.90	\$ 3,668,976	21.80%	\$ 799,895	\$ 4,468,871
30	Engineering & Design	1	LS	\$ 286,763	\$ 286,763	14.91%	\$ 42,748	\$ 329,511
31	Construction Management	1	LS	\$ 539,125	\$ 539,125	14.91%	\$ 80,368	\$ 619,494
<b>Total Contract #2 (WITH Deferred Groins)</b>					<b>\$ 26,522,340</b>		<b>\$ 5,426,471</b>	<b>\$ 31,948,811</b>
<b>Contract 3</b>								
01	Lands & Damages	1	LS	\$ -	\$ -	20.00%	\$ -	\$ -
<b>Total Lands &amp; Damages</b>					<b>\$ -</b>		<b>\$ -</b>	<b>\$ -</b>
17	Beach Replenishment							
	Mobilization and Demobilization	1	LS	\$ 4,014,646	\$ 4,014,646	21.80%	\$ 875,257	\$ 4,889,903
	Hydraulic Beach Fill	4,720,000	CY	\$ 11.70	\$ 55,217,482	21.80%	\$ 12,038,288	\$ 67,255,769
	Shoreline Structures	1	LS	\$ 7,410,126	\$ 7,410,126	21.80%	\$ 1,615,525	\$ 9,025,651
	Sand Fence	75,000	LF	\$ 5	\$ 359,059	21.80%	\$ 78,281	\$ 437,340
	Dune Grass	34	ACR	\$ 19,404	\$ 659,743	21.80%	\$ 143,835	\$ 803,578
<b>Total Beach Replenishment</b>					<b>\$ 67,661,056</b>		<b>\$ 14,751,185</b>	<b>\$ 82,412,240</b>
30	Engineering & Design	1	LS	\$ 13,597,000	\$ 13,597,000	14.91%	\$ 2,026,930	\$ 15,623,930
31	Construction Management	1	LS	\$ 4,639,000	\$ 4,639,000	14.91%	\$ 691,544	\$ 5,330,544
<b>Total Contract #3</b>					<b>\$ 85,897,056</b>		<b>\$ 17,469,658</b>	<b>\$ 103,366,714</b>
<b>Total First Cost (WITHOUT deferred groins)</b>					<b>\$ 139,409,991</b>		<b>\$ 28,366,912</b>	<b>\$ 167,776,903</b>
<b>Total First Cost (WITH deferred groins)</b>					<b>\$ 147,748,363</b>		<b>\$ 30,127,869</b>	<b>\$ 177,876,232</b>

## Table C-2 – Annualized Cost

### Long Beach Island, NY

#### Annualized Cost Summary

<b>First Cost</b> <sup>(a)</sup>	\$	177,876,000
<b>Investment Cost</b>		
Interest During Construction <sup>(b)</sup>	\$	9,162,000
<b>Total Investment Cost:</b>	\$	187,038,000
<b>Annual Costs</b>		
Annualized Investment Cost <sup>(c)</sup>	\$	6,546,000
Annualized Scheduled Renourishment <sup>(d)</sup>	\$	6,178,000
Annualized Major Rehab Cost <sup>(e)</sup>	\$	380,000
Annual Dune & Groin Maintenance Cost <sup>(f)</sup>	\$	453,000
Annual Coastal Monitoring Cost	\$	381,000
<b>Total Annual Cost*</b>	<b>\$</b>	<b>13,938,000</b>

\*October 2013 Price Level

- (a) Total first cost without sunk PED costs (\$1.8M).
- (b) Based on 3 construction contracts: 29, 19 and 25 months of construction @ 3.5% (IDC E&D, RE and Sunk costs calculated separately and included in this total)
- (c)  $I = 3.50\%$  and  $n = 50$  yrs
- (d) From Renourishment Cost Table
- (e) From Annualized Major Rehabilitation Cost Table
- (f) Based 0.5% of initial new groin, groin extension and groin rehabilitation costs from First Cost table on TPCS Plus annualized dune and beach maintenance cost estimated (by the City) to be \$100,000 (Long Beach) + \$50,000 (Town of Hempstead).

**Table C-3 – Renourishment Cost**

**Long Beach Island, NY**

Long Beach Periodic Nourishment Costs  
Recommended Plan

<u>(Per Renourishment)</u>	1,770,000 CY @ \$11.70/CY	\$	20,706,600
	Mob & Demob	\$	4,014,600
	Subtotal	\$	24,722,000
	Contingency 21.59%	\$	5,338,000
	E&D (incl. Contingency of 14.91%)	\$	2,273,000
	Construction Management (incl. Contingency of 14.91%)	\$	2,209,000
	<b>Total Cost Per Operation</b>	<b>\$</b>	<b>34,542,000</b>
	Federal Cost Share: 65%	\$	22,452,300
	Non-Federal Cost Share 35%	\$	12,089,700

YEAR	FUTURE WORK	PRESENT WORTH FACTOR	PRESENT WORTH
0	\$0	1.00000	\$0
5	\$34,542,000	0.84197	\$29,083,437
10	\$34,542,000	0.70892	\$24,487,474
15	\$34,542,000	0.59689	\$20,617,796
20	\$34,542,000	0.50257	\$17,359,631
25	\$34,542,000	0.42315	\$14,616,343
30	\$34,542,000	0.35628	\$12,306,569
35	\$34,542,000	0.29998	\$10,361,801
40	\$34,542,000	0.25257	\$8,724,358
45	\$34,542,000	0.21266	\$7,345,675
<b>SUM OF PRESENT WORTHS</b>	<b>\$310,878,000</b>		<b>\$144,903,084</b>
<b>TOTAL ANNUAL COST</b>			<b>\$6,178,000</b>

Interest Rate 3.50%  
n=50 years 50



# Table C-4 – Major Rehab Cost

## Long Beach Island, NY

Long Beach Major Rehabilitation Costs  
 Recommended Plan  
 Distance: 35,250 LF

Return Interval (yrs)	Frequency	Frequency Interval	Permanent Loss Factor	Erosion Volume (cy/ft)	Emergency Fill (cy/ft)	Emergency Fill Cost (\$/ft)	Average Emergency Fill Cost (\$)	Annual Emergency Fill Cost (\$)	Annual Emergency Fill Cost (\$/ft)
20.00	0.050		0.22	15.00	3.30	\$115.50			
		0.030					\$4,983,733	\$149,512	\$4.24
50.00	0.020		0.27	17.70	4.78	\$167.27			
		0.010					\$6,999,064	\$69,991	\$1.99
100.00	0.010		0.33	19.90	6.57	\$229.85			
		0.005					\$9,208,093	\$46,040	\$1.31
200.00	0.005		0.38	22.00	8.36	\$292.60			
<b>Subtotal Annualized Emergency Fill Cost</b>								<b>\$266,000</b>	<b>\$7.53</b>
<b>Subtotal Emergency Fill (every 5 year total):</b>								<b>\$1,330,000</b>	
<b>Construction Contingency:</b>								<b>\$287,000</b>	
<b>E&amp;D (Incl. Contingency):</b>								<b>\$122,000</b>	
<b>S&amp;A (Incl. Contingency):</b>								<b>\$160,000</b>	
<b>Total Emergency Fill Cost (every 5 year total):</b>								<b>\$1,899,000</b>	
<b>Total Emergency Fill for Project (9 Cycles):</b>								<b>\$17,091,000</b>	
<b>Total Annualized Emergency Fill Cost:</b>								<b>\$380,000</b>	

Notes:

Loss Factor: This is the percent of eroded volume permanently lost to the profile. The factors are based on experience at Ocean City, Md.  
 Erosion Volume: Maximum erosion volume landward of a given profile position computed from SBEACH (50, 100 and 200 year storms extrapolated from northeasters)  
 Emergency Fill Cost: Based on for trucked sand (cy) = \$35

Table C-5 – Monitoring Cost

Long Beach Island, NY

Long Beach Coastal Monitoring Costs

YEAR	FUTURE WORTH (Incl Contingency)	PRESENT WORTH FACTOR	PRESENT WORTH
1	\$814,650	0.96618	\$787,101
2	\$492,440	0.93351	\$459,698
3	\$492,440	0.90194	\$444,153
4	\$492,440	0.87144	\$429,133
5	\$924,080	0.84197	\$778,051
6	\$249,260	0.81350	\$202,773
7	\$322,210	0.78599	\$253,254
8	\$249,260	0.75941	\$189,291
9	\$322,210	0.73373	\$236,415
10	\$407,330	0.70892	\$288,764
11	\$322,210	0.68495	\$220,696
12	\$249,260	0.66178	\$164,956
13	\$322,210	0.63940	\$206,022
14	\$249,260	0.61778	\$153,988
15	\$571,470	0.59689	\$341,105
16	\$249,260	0.57671	\$143,750
17	\$322,210	0.55720	\$179,537
18	\$249,260	0.53836	\$134,192
19	\$322,210	0.52016	\$167,599
20	\$407,330	0.50257	\$204,710
21	\$322,210	0.48557	\$156,456
22	\$249,260	0.46915	\$116,940
23	\$322,210	0.45329	\$146,053
24	\$249,260	0.43796	\$109,165
25	\$480,280	0.42315	\$203,229
26	\$249,260	0.40884	\$101,907
27	\$322,210	0.39501	\$127,277
28	\$249,260	0.38165	\$95,131
29	\$322,210	0.36875	\$118,814
30	\$498,520	0.35628	\$177,612
31	\$322,210	0.34423	\$110,914
32	\$249,260	0.33259	\$82,901
33	\$322,210	0.32134	\$103,540
34	\$249,260	0.31048	\$77,389
35	\$480,280	0.29998	\$144,073
36	\$249,260	0.28983	\$72,244
37	\$322,210	0.28003	\$90,229
38	\$249,260	0.27056	\$67,440
39	\$322,210	0.26141	\$84,230
40	\$407,330	0.25257	\$102,880
41	\$322,210	0.24403	\$78,629
42	\$249,260	0.23578	\$58,770
43	\$322,210	0.22781	\$73,401
44	\$249,260	0.22010	\$54,863
45	\$571,470	0.21266	\$121,528
46	\$249,260	0.20547	\$51,215
47	\$322,210	0.19852	\$63,965
48	\$249,260	0.19181	\$47,810
49	\$322,210	0.18532	\$59,712
50	\$249,260	0.17905	\$44,631
Contingency %:	21.59%		
Sum of Present Worths:	\$17,576,000		\$8,928,140
<b>TOTAL ANNUAL COST</b>			<b>\$381,000</b>

**Long Beach Island, NY**

**Long Beach Coastal Monitoring Costs - Breakdown**

	<b>BEACH PROFILES</b>	<b>SEDIMENT SAMPLES</b>	<b>AERIALS</b>	<b>WAVE GAUGES</b>	<b>DATA ANALYSIS (REPORT)</b>	<b>BORROW AREA MONITORING</b>	<b>TOTAL</b>
Year 1	\$205,000	\$80,000	\$120,000	\$190,000	\$75,000		\$670,000
Year 2	\$205,000		\$60,000	\$140,000			\$405,000
Year 3	\$205,000		\$60,000	\$140,000			\$405,000
Year 4	\$205,000		\$60,000	\$140,000			\$405,000
Year 5	\$205,000	\$40,000	\$60,000	\$140,000	\$75,000	\$240,000	\$760,000
Year 6	\$205,000						\$205,000
Year 7	\$205,000		\$60,000				\$265,000
Year 8	\$205,000						\$205,000
Year 9	\$205,000		\$60,000				\$265,000
Year 10	\$205,000	\$40,000				\$90,000	\$335,000
Year 11	\$205,000		\$60,000				\$265,000
Year 12	\$205,000						\$205,000
Year 13	\$205,000		\$60,000				\$265,000
Year 14	\$205,000						\$205,000
Year 15	\$205,000	\$40,000	\$60,000		\$75,000	\$90,000	\$470,000
Year 16	\$205,000						\$205,000
Year 17	\$205,000		\$60,000				\$265,000
Year 18	\$205,000						\$205,000
Year 19	\$205,000		\$60,000				\$265,000
Year 20	\$205,000	\$40,000				\$90,000	\$335,000
Year 21	\$205,000		\$60,000				\$265,000
Year 22	\$205,000						\$205,000
Year 23	\$205,000		\$60,000				\$265,000
Year 24	\$205,000						\$205,000
Year 25	\$205,000	\$40,000	\$60,000			\$90,000	\$395,000
Year 26	\$205,000						\$205,000
Year 27	\$205,000		\$60,000				\$265,000
Year 28	\$205,000						\$205,000
Year 29	\$205,000		\$60,000				\$265,000
Year 30	\$205,000	\$40,000			\$75,000	\$90,000	\$410,000
Year 31	\$205,000		\$60,000				\$265,000
Year 32	\$205,000						\$205,000
Year 33	\$205,000		\$60,000				\$265,000
Year 34	\$205,000						\$205,000
Year 35	\$205,000	\$40,000	\$60,000			\$90,000	\$395,000
Year 36	\$205,000						\$205,000
Year 37	\$205,000		\$60,000				\$265,000
Year 38	\$205,000						\$205,000
Year 39	\$205,000		\$60,000				\$265,000
Year 40	\$205,000	\$40,000				\$90,000	\$335,000
Year 41	\$205,000		\$60,000				\$265,000
Year 42	\$205,000						\$205,000
Year 43	\$205,000		\$60,000				\$265,000
Year 44	\$205,000						\$205,000
Year 45	\$205,000	\$40,000	\$60,000		\$75,000	\$90,000	\$470,000
Year 46	\$205,000						\$205,000
Year 47	\$205,000		\$60,000				\$265,000
Year 48	\$205,000						\$205,000
Year 49	\$205,000		\$60,000				\$265,000
Year 50	\$205,000						\$205,000

NOTES:

INTEREST = 3.500%

PROJ.LIFE = 50

CAPITAL RECOVERY FACTOR = 0.04263

**Table C-6 – Cost Apportionment**

<b>Long Beach Island, NY</b>			
<b>Cost Apportionment</b>			
Cost-Sharing	Federal Share	Non-Federal Share	Total
<b>Project First Costs</b>			
Cash Contribution	\$ 177,702,000	\$ -	\$ 177,702,000
Real Estate Lands & Damages	\$ 174,000	\$ -	\$ 174,000
<b>TOTAL FIRST COST</b>	<b>\$ 177,876,000</b>	<b>\$ -</b>	<b>\$ 177,876,000</b>
<b>Continuing Construction First Cost</b>			
Scheduled Beach Renourishment <sup>(a)</sup>	\$ 202,071,000	\$ 108,807,000	\$ 310,878,000
Emergency Beach Fill <sup>(b)</sup>	\$ 11,109,000	\$ 5,982,000	\$ 17,091,000
Coastal Monitoring <sup>(c)</sup>	\$ 11,424,000	\$ 6,152,000	\$ 17,576,000
<b>SUBTOTAL CONTINUING CONSTRUCTION COST</b>	<b>\$ 224,604,000</b>	<b>\$ 120,941,000</b>	<b>\$ 345,545,000</b>
<b>TOTAL CUMULATIVE CONSTRUCTION COST (d)</b>	<b>\$ 402,480,000</b>	<b>\$ 120,941,000</b>	<b>\$ 523,421,000</b>
Annual Beach & Groin Maintenance Cost	\$ -	\$ 453,000	\$ 453,000
<b>TOTAL ANNUAL O&amp;M COSTS</b>	<b>\$ -</b>	<b>\$ 453,000</b>	<b>\$ 453,000</b>
* October 2013 Price Level			
** Shared based on 65% Federal and 35% non-Federal for construction and renourishment			
(a) Beach Renourishment = \$34,542,000 every 5-year cycle for 9 cycles			
(b) Emergency Beach Fill = \$1,899,000 every 5-year cycle for 9 cycles			
(c) Coastal Monitoring Varies yearly and is broken dow in the Coastal Monitoring Cost Table			
(d) Cumulative Costs include Total First Cost and Cumulative Construction			

# Total Project Cost Summary

PROJECT: Long Beach Island, NY      DISTRICT: NAN New York      PREPARED: 2/3/2014  
 PROJECT NO: -      POC: CHIEF, COST ENGINEERING, Mukesh Kumar  
 LOCATION: Long Beach Island, NY

This Estimate reflects the scope and schedule in report; Long Beach NY HSLRR

Civil Works Work Breakdown Structure		ESTIMATED COST				PROJECT FIRST COST (Constant Dollar Basis)				TOTAL PROJECT COST (FULLY FUNDED)				
WBS NUMBER A	Civil Works Feature & Sub-Feature Description B	COST (\$K) C	CNTG (\$K) D	CNTG (%) E	TOTAL (\$K) F	Program Year (Budget EC): 2014 Effective Price Level Date: 1 OCT 13				Spent Thru: 1-Oct-13 (\$K) K	L	COST (\$K) M	CNTG (\$K) N	FULL (\$K) O
						ESC (%) G	COST (\$K) H	CNTG (\$K) I	TOTAL (\$K) J					
10	BREAKWATER & SEAWALLS	\$49,758	\$10,848	21.80%	\$60,606	0.0%	\$49,758	\$10,848	\$60,606	\$0		\$51,533	\$11,235	\$62,768
17	BEACH REPLENISHMENT	\$67,661	\$14,751	21.80%	\$82,412	0.0%	\$67,661	\$14,751	\$82,412	\$0		\$71,546	\$15,598	\$87,144
<b>CONSTRUCTION ESTIMATE TOTALS:</b>		\$117,419	\$25,599	21.80%	\$143,019		\$117,419	\$25,599	\$143,019			\$123,078	\$26,833	\$149,912
01	LANDS AND DAMAGES	\$145	\$29	20.00%	\$174	0.0%	\$145	\$29	\$174	\$0		\$148	\$30	\$177
30	PLANNING, ENGINEERING & DESIGN	\$21,684	\$3,232	14.91%	\$24,916	0.0%	\$21,684	\$3,232	\$24,916	\$1,800		\$23,316	\$3,476	\$28,591
31	CONSTRUCTION MANAGEMENT	\$8,500	\$1,267	14.91%	\$9,767	0.0%	\$8,500	\$1,267	\$9,767	\$0		\$8,909	\$1,328	\$10,238
<b>PROJECT COST TOTALS:</b>		\$147,748	\$30,128		\$177,876		\$147,748	\$30,128	\$177,876	\$1,800		\$155,451	\$31,666	\$188,918
17	BEACH REPLENISHMENT (Renourishme)	\$248,923	\$53,746	21.59%	\$302,669	0.0%	\$248,923	\$53,746	\$302,669	\$0		\$442,602	\$95,564	\$538,166
<b>CONSTRUCTION ESTIMATE TOTALS:</b>		\$248,923	\$53,746	21.59%	\$302,669		\$248,923	\$53,746	\$302,669			\$442,602	\$95,564	\$538,166
30	PLANNING, ENGINEERING & DESIGN (Renourishme)	\$18,756	\$2,799	14.92%	\$21,555	0.0%	\$18,756	\$2,799	\$21,555	\$0		\$119,764	\$17,873	\$137,637
31	CONSTRUCTION MANAGEMENT (Renourishme)	\$18,549	\$2,772	14.94%	\$21,321	0.0%	\$18,549	\$2,772	\$21,321	\$0		\$33,126	\$4,950	\$38,077
<b>PROJECT COST TOTALS:</b>		\$286,228	\$59,317		\$345,545		\$286,228	\$59,317	\$345,545	\$0		\$595,492	\$118,387	\$713,880
<u>Mandatory by Regulation</u>		CHIEF, COST ENGINEERING, Mukesh Kumar										ESTIMATED FEDERAL COST: 100%		\$188,918
<u>Mandatory by Regulation</u>		PROJECT MANAGER, Ron Pinzon										ESTIMATED NON-FEDERAL COST: 0%		\$0
<u>Mandatory by Regulation</u>		CHIEF, REAL ESTATE, Noreen Dresser										<b>ESTIMATED TOTAL PROJECT COST:</b>		\$188,918
		CHIEF, PLANNING, Frank Santomauro										ESTIMATED FEDERAL COST: 65%		\$464,022
		CHIEF, ENGINEERING, Arthur Connolly										ESTIMATED NON-FEDERAL COST: 35%		\$249,858
		CHIEF, OPERATIONS, Tom Creamer										<b>ESTIMATED RENOURISHMENT TOTAL PROJECT COST:</b>		\$713,880
		CHIEF, CONSTRUCTION, Gerald Byrne												
		CHIEF, CONTRACTING, Frank Cashman												
		CHIEF, PM-PB, Anthony Ciorra												
		CHIEF, DPM, Joseph Seebode												

# Total Project Cost Summary (cont.)

\*\*\*\* CONTRACT COST SUMMARY \*\*\*\*

PROJECT: Long Beach Island, NY  
 LOCATION: Long Beach Island, NY  
 This Estimate reflects the scope and schedule in report;

Long Beach NY HSLRR

DISTRICT: NAN New York  
 POC: CHIEF, COST ENGINEERING, Mukesh Kumar  
 PREPARED: 2/3/2014

Civil Works Work Breakdown Structure		ESTIMATED COST				PROJECT FIRST COST (Constant Dollar Basis)				TOTAL PROJECT COST (FULLY FUNDED)				
		Estimate Prepared: 2/3/2014				Program Year (Budget EC): 2014								
		Effective Price Level: 41548				Effective Price Level Date: 1 OCT 13								
		RISK BASED												
WBS	Civil Works	COST	CNTG	CNTG	TOTAL	ESC	COST	CNTG	TOTAL	Mid-Point	INFLATED	COST	CNTG	FULL
NUMBER	Feature & Sub-Feature Description	(\$K)	(\$K)	(%)	(\$K)	(%)	(\$K)	(\$K)	(\$K)	Date	(%)	(\$K)	(\$K)	(\$K)
<u>A</u>	<u>B</u>	<u>C</u>	<u>D</u>	<u>E</u>	<u>F</u>	<u>G</u>	<u>H</u>	<u>I</u>	<u>J</u>	<u>P</u>	<u>L</u>	<u>M</u>	<u>N</u>	<u>O</u>
<b>Contract #1</b>														
10	BREAKWATER & SEAWALLS	\$28,397	\$6,191	21.80%	\$34,588	0.0%	\$28,397	\$6,191	\$34,588	2016Q1	3.8%	\$29,467	\$6,424	\$35,892
<b>CONSTRUCTION ESTIMATE TOTALS:</b>		\$28,397	\$6,191	21.80%	\$34,588	\$28,397	\$6,191	\$34,588	\$29,467	\$6,424	\$35,892			
01	LANDS AND DAMAGES	\$145	\$29	20.00%	\$174	0.0%	\$145	\$29	\$174	2015Q1	1.8%	\$148	\$30	\$177
30	PLANNING, ENGINEERING & DESIGN													
2.50%	Project Management	\$710	\$106	14.91%	\$816	0.0%	\$710	\$106	\$816	2015Q1	3.7%	\$736	\$110	\$846
1.00%	Planning & Environmental Compliance	\$284	\$42	14.91%	\$326	0.0%	\$284	\$42	\$326	2015Q1	3.7%	\$294	\$44	\$338
7.75%	Engineering & Design	\$2,201	\$328	14.91%	\$2,529	0.0%	\$2,201	\$328	\$2,529	2015Q1	3.7%	\$2,282	\$340	\$2,622
1.00%	Reviews, ATRs, IEPs, VE	\$284	\$42	14.91%	\$326	0.0%	\$284	\$42	\$326	2015Q1	3.7%	\$294	\$44	\$338
0.25%	Life Cycle Updates (cost, schedule, risks)	\$71	\$11	14.91%	\$82	0.0%	\$71	\$11	\$82	2015Q1	3.7%	\$74	\$11	\$85
0.25%	Contracting & Reprographics	\$71	\$11	14.91%	\$82	0.0%	\$71	\$11	\$82	2015Q1	3.7%	\$74	\$11	\$85
1.50%	Engineering During Construction	\$426	\$64	14.91%	\$490	0.0%	\$426	\$64	\$490	2016Q1	8.0%	\$460	\$69	\$529
1.00%	Planning During Construction	\$284	\$42	14.91%	\$326	0.0%	\$284	\$42	\$326	2016Q1	8.0%	\$307	\$46	\$352
1.00%	Project Operations	\$284	\$42	14.91%	\$326	0.0%	\$284	\$42	\$326	2015Q1	3.7%	\$294	\$44	\$338
31	CONSTRUCTION MANAGEMENT													
7.65%	Construction Management	\$2,172	\$324	14.91%	\$2,496	0.0%	\$2,172	\$324	\$2,496	2016Q1	3.8%	\$2,255	\$336	\$2,592
0.00%	Project Operation:	\$0	\$0	14.91%	\$0	0.0%	\$0	\$0	\$0	0	0.0%	\$0	\$0	\$0
0.00%	Project Management	\$0	\$0	14.91%	\$0	0.0%	\$0	\$0	\$0	0	0.0%	\$0	\$0	\$0
<b>CONTRACT COST TOTALS:</b>		\$35,329	\$7,232		\$42,561	\$35,329	\$7,232	\$42,561	\$36,685	\$7,508	\$44,193			

# Total Project Cost Summary (cont.)

\*\*\*\* CONTRACT COST SUMMARY \*\*\*\*

PROJECT: Long Beach Island, NY  
 LOCATION: Long Beach Island, NY  
 This Estimate reflects the scope and schedule in report:

Long Beach NY HSLRR

DISTRICT: NAN New York  
 POC: CHIEF, COST ENGINEERING, Mukesh Kumar  
 PREPARED: 2/3/2014

Civil Works Work Breakdown Structure		ESTIMATED COST				PROJECT FIRST COST (Constant Dollar Basis)				TOTAL PROJECT COST (FULLY FUNDED)				
		Estimate Prepared: 2/3/2014		Effective Price Level: 41548		Program Year (Budget EC): 2014		Effective Price Level Date: 1 OCT 13						
WBS NUMBER	Civil Works Feature & Sub-Feature Description	COST (\$K)	CNTG (\$K)	CNTG (%)	TOTAL (\$K)	ESC (%)	COST (\$K)	CNTG (\$K)	TOTAL (\$K)	Mid-Point Date	INFLATED (%)	COST (\$K)	CNTG (\$K)	FULL (\$K)
A	B	C	D	E	F	G	H	I	J	P	L	M	N	O
	<b>Contract #2</b>													
10	BREAKWATER & SEAWALLS	\$21,361	\$4,657	21.80%	\$26,018	0.0%	\$21,361	\$4,657	\$26,018	2015Q4	3.3%	\$22,065	\$4,811	\$26,876
<b>CONSTRUCTION ESTIMATE TOTALS:</b>		\$21,361	\$4,657	21.80%	\$26,018		\$21,361	\$4,657	\$26,018			\$22,065	\$4,811	\$26,876
01	LANDS AND DAMAGES	\$0	\$0	20.00%	\$0	0.0%	\$0	\$0	\$0	0	0.0%	\$0	\$0	\$0
30	PLANNING, ENGINEERING & DESIGN													
2.50%	Project Management	\$534	\$80	14.91%	\$614	0.0%	\$534	\$80	\$614	2015Q1	3.7%	\$554	\$83	\$636
1.00%	Planning & Environmental Compliance	\$214	\$32	14.91%	\$246	0.0%	\$214	\$32	\$246	2015Q1	3.7%	\$222	\$33	\$255
7.75%	Engineering & Design	\$1,656	\$247	14.91%	\$1,903	0.0%	\$1,656	\$247	\$1,903	2015Q1	3.7%	\$1,717	\$256	\$1,972
1.00%	Reviews, ATRs, IEPRs, VE	\$214	\$32	14.91%	\$246	0.0%	\$214	\$32	\$246	2015Q1	3.7%	\$222	\$33	\$255
0.25%	Life Cycle Updates (cost, schedule, risks)	\$53	\$8	14.91%	\$61	0.0%	\$53	\$8	\$61	2015Q1	3.7%	\$55	\$8	\$63
0.25%	Contracting & Reprographics	\$53	\$8	14.91%	\$61	0.0%	\$53	\$8	\$61	2015Q1	3.7%	\$55	\$8	\$63
1.50%	Engineering During Construction	\$320	\$48	14.91%	\$368	0.0%	\$320	\$48	\$368	2015Q4	6.9%	\$342	\$51	\$393
1.00%	Planning During Construction	\$214	\$32	14.91%	\$246	0.0%	\$214	\$32	\$246	2015Q4	6.9%	\$229	\$34	\$263
1.00%	Project Operations	\$214	\$32	14.91%	\$246	0.0%	\$214	\$32	\$246	2015Q1	3.7%	\$222	\$33	\$255
31	CONSTRUCTION MANAGEMENT													
7.91%	Construction Management	\$1,689	\$252	14.91%	\$1,941	0.0%	\$1,689	\$252	\$1,941	2015Q4	3.4%	\$1,746	\$260	\$2,006
0.00%	Project Operation:	\$0	\$0	14.91%	\$0	0.0%	\$0	\$0	\$0	0	0.0%	\$0	\$0	\$0
0.00%	Project Management	\$0	\$0	14.91%	\$0	0.0%	\$0	\$0	\$0	0	0.0%	\$0	\$0	\$0
<b>CONTRACT COST TOTALS:</b>		\$26,522	\$5,426		\$31,949		\$26,522	\$5,426	\$31,949			\$27,427	\$5,610	\$33,037

# Total Project Cost Summary (cont.)

\*\*\*\* CONTRACT COST SUMMARY \*\*\*\*

PROJECT: Long Beach Island, NY  
 LOCATION: Long Beach Island, NY  
 This Estimate reflects the scope and schedule in report:

Long Beach NY HSLRR

DISTRICT: NAN New York  
 POC: CHIEF, COST ENGINEERING, Mukesh Kumar  
 PREPARED: 2/3/2014

Civil Works Work Breakdown Structure		ESTIMATED COST				PROJECT FIRST COST (Constant Dollar Basis)				TOTAL PROJECT COST (FULLY FUNDED)				
		Estimate Prepared: 2/3/2014 Effective Price Level: 41548				Program Year (Budget EC): 2014 Effective Price Level Date: 1 OCT 13								
WBS NUMBER	Civil Works Feature & Sub-Feature Description	COST (\$K)	CNTG (\$K)	CNTG (%)	TOTAL (\$K)	ESC (%)	COST (\$K)	CNTG (\$K)	TOTAL (\$K)	Mid-Point Date	INFLATED (%)	COST (\$K)	CNTG (\$K)	FULL (\$K)
A	B	C	D	E	F	G	H	I	J	P	L	M	N	O
17	<b>Contract #3</b> BEACH REPLENISHMENT	\$67,661	\$14,751	21.80%	\$82,412	0.0%	\$67,661	\$14,751	\$82,412	2017Q1	5.7%	\$71,546	\$15,598	\$87,144
<b>CONSTRUCTION ESTIMATE TOTALS:</b>		\$67,661	\$14,751	21.80%	\$82,412	\$67,661	\$14,751	\$82,412				\$71,546	\$15,598	\$87,144
01	LANDS AND DAMAGES	\$0	\$0	20.00%	\$0	0.0%	\$0	\$0	\$0	0	0.0%	\$0	\$0	\$0
30	PLANNING, ENGINEERING & DESIGN													
2.50%	Project Management	\$1,692	\$252	14.91%	\$1,944	0.0%	\$1,692	\$252	\$1,944	2016Q1	8.0%	\$1,828	\$272	\$2,100
1.00%	Planning & Environmental Compliance	\$677	\$101	14.91%	\$778	0.0%	\$677	\$101	\$778	2016Q1	8.0%	\$731	\$109	\$840
7.75%	Engineering & Design	\$5,244	\$782	14.91%	\$6,026	0.0%	\$5,244	\$782	\$6,026	2016Q1	8.0%	\$5,664	\$844	\$6,509
1.00%	Reviews, ATRs, IEPs, VE	\$677	\$101	14.91%	\$778	0.0%	\$677	\$101	\$778	2016Q1	8.0%	\$731	\$109	\$840
0.25%	Life Cycle Updates (cost, schedule, risks)	\$169	\$25	14.91%	\$194	0.0%	\$169	\$25	\$194	2016Q1	8.0%	\$183	\$27	\$210
0.25%	Contracting & Reprographics	\$169	\$25	14.91%	\$194	0.0%	\$169	\$25	\$194	2016Q1	8.0%	\$183	\$27	\$210
1.50%	Engineering During Construction	\$1,015	\$151	14.91%	\$1,166	0.0%	\$1,015	\$151	\$1,166	2017Q1	12.6%	\$1,143	\$170	\$1,314
1.00%	Planning During Construction	\$3,277	\$489	14.91%	\$3,766	0.0%	\$3,277	\$489	\$3,766	2017Q1	12.6%	\$3,691	\$550	\$4,241
1.00%	Project Operations	\$677	\$101	14.91%	\$778	0.0%	\$677	\$101	\$778	2016Q1	8.0%	\$731	\$109	\$840
31	CONSTRUCTION MANAGEMENT													
6.86%	Construction Management	\$4,639	\$692	14.91%	\$5,331	0.0%	\$4,639	\$692	\$5,331	2017Q1	5.8%	\$4,908	\$732	\$5,640
0.00%	Project Operation:	\$0	\$0	14.91%	\$0	0.0%	\$0	\$0	\$0	0	0.0%	\$0	\$0	\$0
0.00%	Project Management	\$0	\$0	14.91%	\$0	0.0%	\$0	\$0	\$0	0	0.0%	\$0	\$0	\$0
<b>CONTRACT COST TOTALS:</b>		\$85,897	\$17,470		\$103,367	\$85,897	\$17,470	\$103,367				\$91,339	\$18,549	\$109,887

**Taylor Canfield:**  
 Includes \$600K for Cultural Resources and \$2M for Clean Air Act.



# Total Project Cost Summary (cont.)

**** CONTRACT COST SUMMARY ****															
PROJECT: Long Beach Island, NY			DISTRICT: NAN New York			PREPARED: 2/3/2014									
LOCATION: Long Beach Island, NY			POC: CHIEF, COST ENGINEERING, Mukesh Kumar												
This Estimate reflects the scope and schedule in report:			Long Beach NY HSLRR												
Civil Works Work Breakdown Structure			ESTIMATED COST				PROJECT FIRST COST (Constant Dollar Basis)				TOTAL PROJECT COST (FULLY FUNDED)				
			Estimate Prepared: 2/3/2014 Effective Price Level: 41548				Program Year (Budget EC): 2014 Effective Price Level Date: 1 OCT 13								
WBS NUMBER	Civil Works Feature & Sub-Feature Description	Year	COST (\$K)	CNTG (\$K)	CNTG (%)	TOTAL (\$K)	ESC (%)	COST (\$K)	CNTG (\$K)	TOTAL (\$K)	Mid-Point Date	INFLATED (%)	COST (\$K)	CNTG (\$K)	FULL (\$K)
A	B		C	D	E	F	G	H	I	J	P	L	M	N	O
<b>Renourishment Activities</b>															
17	BEACH REPLENISHMENT	Yr 5	\$29,972	\$6,471	21.59%	\$36,443	0.0%	\$29,972	\$6,471	\$36,443	2023Q2	18.9%	\$35,651	\$7,697	\$43,349
17	BEACH REPLENISHMENT	Yr 10	\$27,462	\$5,930	21.59%	\$33,392	0.0%	\$27,462	\$5,930	\$33,392	2028Q2	30.7%	\$35,889	\$7,750	\$43,639
17	BEACH REPLENISHMENT	Yr 15	\$27,327	\$5,900	21.59%	\$33,227	0.0%	\$27,327	\$5,900	\$33,227	2033Q2	43.6%	\$39,237	\$8,471	\$47,708
17	BEACH REPLENISHMENT	Yr 20	\$27,387	\$5,913	21.59%	\$33,300	0.0%	\$27,387	\$5,913	\$33,300	2038Q2	57.8%	\$43,204	\$9,328	\$52,531
17	BEACH REPLENISHMENT	Yr 25	\$27,402	\$5,917	21.59%	\$33,319	0.0%	\$27,402	\$5,917	\$33,319	2043Q2	73.3%	\$47,493	\$10,255	\$57,748
17	BEACH REPLENISHMENT	Yr 30	\$27,387	\$5,913	21.59%	\$33,300	0.0%	\$27,387	\$5,913	\$33,300	2048Q2	90.4%	\$52,151	\$11,260	\$63,410
17	BEACH REPLENISHMENT	Yr 35	\$27,327	\$5,900	21.59%	\$33,227	0.0%	\$27,327	\$5,900	\$33,227	2053Q2	109.2%	\$57,171	\$12,344	\$69,515
17	BEACH REPLENISHMENT	Yr 40	\$27,462	\$5,930	21.59%	\$33,392	0.0%	\$27,462	\$5,930	\$33,392	2058Q2	129.9%	\$63,123	\$13,630	\$76,754
17	BEACH REPLENISHMENT	Yr 45	\$27,197	\$5,872	21.59%	\$33,069	0.0%	\$27,197	\$5,872	\$33,069	2063Q2	152.5%	\$68,683	\$14,829	\$83,512
<b>CONSTRUCTION ESTIMATE TOTALS:</b>			\$248,923	\$53,746	21.59%	\$302,669		\$248,923	\$53,746	\$302,669			\$442,602	\$95,564	\$538,166
30	PLANNING, ENGINEERING & DESIGN														
8.00%	PED Costs - 8% of Renourish/Major Rehab Only	Yr 5	\$2,084	\$311	14.91%	\$2,395	0.0%	\$2,084	\$311	\$2,395	2022Q4	43.8%	\$2,996	\$447	\$3,443
8.00%	PED Costs - 8% of Renourish/Major Rehab Only	Yr 10	\$2,084	\$311	14.91%	\$2,395	0.0%	\$2,084	\$311	\$2,395	2027Q4	80.5%	\$3,762	\$561	\$4,324
8.00%	PED Costs - 8% of Renourish/Major Rehab Only	Yr 15	\$2,084	\$311	14.91%	\$2,395	0.0%	\$2,084	\$311	\$2,395	2032Q4	131.9%	\$4,832	\$721	\$5,553
8.00%	PED Costs - 8% of Renourish/Major Rehab Only	Yr 20	\$2,084	\$311	14.91%	\$2,395	0.0%	\$2,084	\$311	\$2,395	2037Q4	205.2%	\$6,361	\$949	\$7,310
8.00%	PED Costs - 8% of Renourish/Major Rehab Only	Yr 25	\$2,084	\$311	14.91%	\$2,395	0.0%	\$2,084	\$311	\$2,395	2042Q4	312.3%	\$8,593	\$1,282	\$9,876
8.00%	PED Costs - 8% of Renourish/Major Rehab Only	Yr 30	\$2,084	\$311	14.91%	\$2,395	0.0%	\$2,084	\$311	\$2,395	2047Q4	473.0%	\$11,941	\$1,782	\$13,723
8.00%	PED Costs - 8% of Renourish/Major Rehab Only	Yr 35	\$2,084	\$311	14.91%	\$2,395	0.0%	\$2,084	\$311	\$2,395	2052Q4	720.8%	\$17,105	\$2,553	\$19,658
8.00%	PED Costs - 8% of Renourish/Major Rehab Only	Yr 40	\$2,084	\$311	14.91%	\$2,395	0.0%	\$2,084	\$311	\$2,395	2057Q4	1114.5%	\$25,311	\$3,777	\$29,088
8.00%	PED Costs - 8% of Renourish/Major Rehab Only	Yr 45	\$2,084	\$311	14.91%	\$2,395	0.0%	\$2,084	\$311	\$2,395	2062Q4	1764.8%	\$38,862	\$5,799	\$44,661
31	CONSTRUCTION MANAGEMENT														
7.77%	S&A Costs - Calc'd on Renourish/Major Rehab ONLY	Yr 5	\$2,061	\$308	14.91%	\$2,369	0.0%	\$2,061	\$308	\$2,369	2023Q2	19.0%	\$2,453	\$367	\$2,820
7.47%	S&A Costs - Calc'd on Renourish/Major Rehab ONLY	Yr 10	\$2,061	\$308	14.91%	\$2,369	0.0%	\$2,061	\$308	\$2,369	2028Q2	30.8%	\$2,695	\$403	\$3,098
7.47%	S&A Costs - Calc'd on Renourish/Major Rehab ONLY	Yr 15	\$2,061	\$308	14.91%	\$2,369	0.0%	\$2,061	\$308	\$2,369	2033Q2	43.7%	\$2,961	\$443	\$3,404
7.47%	S&A Costs - Calc'd on Renourish/Major Rehab ONLY	Yr 20	\$2,061	\$308	14.91%	\$2,369	0.0%	\$2,061	\$308	\$2,369	2038Q2	57.8%	\$3,253	\$486	\$3,739
7.47%	S&A Costs - Calc'd on Renourish/Major Rehab ONLY	Yr 25	\$2,061	\$308	14.91%	\$2,369	0.0%	\$2,061	\$308	\$2,369	2043Q2	73.4%	\$3,574	\$534	\$4,108
7.47%	S&A Costs - Calc'd on Renourish/Major Rehab ONLY	Yr 30	\$2,061	\$308	14.91%	\$2,369	0.0%	\$2,061	\$308	\$2,369	2048Q2	90.5%	\$3,927	\$587	\$4,514
7.47%	S&A Costs - Calc'd on Renourish/Major Rehab ONLY	Yr 35	\$2,061	\$308	14.91%	\$2,369	0.0%	\$2,061	\$308	\$2,369	2053Q2	109.3%	\$4,314	\$645	\$4,959
7.47%	S&A Costs - Calc'd on Renourish/Major Rehab ONLY	Yr 40	\$2,061	\$308	14.91%	\$2,369	0.0%	\$2,061	\$308	\$2,369	2058Q2	130.0%	\$4,740	\$708	\$5,449
7.47%	S&A Costs - Calc'd on Renourish/Major Rehab ONLY	Yr 45	\$2,061	\$308	14.91%	\$2,369	0.0%	\$2,061	\$308	\$2,369	2063Q2	152.7%	\$5,208	\$778	\$5,986
<b>CONTRACT COST TOTALS:</b>			\$286,228	\$59,317		\$345,545		\$286,228	\$59,317	\$345,545			\$595,492	\$118,387	\$713,880

# Abbreviated Risk Analysis (ARA) Results


## Abbreviated Risk Analysis

Project (less than \$40M): **Long Beach, NY**  
 Project Development Stage: **Feasibility (Recommended Plan)**  
 Risk Category: **Moderate Risk: Typical Project or Possible Life Safety**

Total Construction Contract Cost = \$ **117,419,353**

	CWWBS	Feature of Work	Contract Cost	% Contingency	\$ Contingency	Total
	01 LANDS AND DAMAGES	Real Estate	\$ 145,010	20.00%	\$ 29,002	\$ 174,012.00
1	17 BEACH REPLENISHMENT	Mobilization and Demobilization	\$ 4,014,646	13.38%	\$ 537,319	\$ 4,551,965.15
2	17 BEACH REPLENISHMENT	Dredging From Borrow area	\$ 39,931,200	21.59%	\$ 8,620,922	\$ 48,552,121.54
3	17 BEACH REPLENISHMENT	Shore Crew	\$ 13,026,351	17.44%	\$ 2,272,246	\$ 15,298,596.52
4	10 BREAKWATERS AND SEAWALLS	Core/Bedding Stone	\$ 9,165,067	24.80%	\$ 2,273,264	\$ 11,438,331.50
5	10 BREAKWATERS AND SEAWALLS	Class D Armor Stone	\$ 7,169,141	24.80%	\$ 1,778,203	\$ 8,947,344.18
6	10 BREAKWATERS AND SEAWALLS	Class B/C Armor Stone	\$ 26,837,698	24.80%	\$ 6,656,708	\$ 33,494,405.71
7	10 BREAKWATERS AND SEAWALLS	Steel Sheet Piling	\$ 1,919,730	16.28%	\$ 312,612	\$ 2,232,341.23
8	17 BEACH REPLENISHMENT	Timber Pedestrian Dune Walkovers - ADA	\$ 3,411,557	13.20%	\$ 450,412	\$ 3,861,968.09
12		Remaining Construction Items	\$ 11,943,963	11.3%	\$ 2,666,150	\$ 14,610,112.62
13	30 PLANNING, ENGINEERING, AND DESIGN	Planning, Engineering, & Design	\$ 21,684,000	14.91%	\$ 3,232,473	\$ 24,916,473.40
14	31 CONSTRUCTION MANAGEMENT	Construction Management	\$ 8,500,000	14.91%	\$ 1,267,110	\$ 9,767,110.49
<b>Totals</b>						
		Real Estate	\$ 145,010	20.00%	\$ 29,002	\$ 174,012.00
		Total Construction Estimate	\$ 117,419,353	21.77%	\$ 25,567,834	\$ 142,987,187
		Total Planning, Engineering & Design	\$ 21,684,000	14.91%	\$ 3,232,473	\$ 24,916,473
		Total Construction Management	\$ 8,500,000	14.91%	\$ 1,267,110	\$ 9,767,110
		<b>Total</b>	<b>\$ 147,748,363</b>		<b>\$ 30,096,420</b>	<b>\$ 177,844,782</b>

# Schedule



## DQC Comments/Responses

### District Quality Control (DQC) Comments

#### Long Beach Island, New York Hurricane and Storm Damage Reduction Limited Reevaluation Report

By: Anthony Schiano

Date: 10-28-13

#### Responses by Taylor Canfield

Back checked by Anthony Schiano

#### Cost appendix

Please include a table of contents. – **Will do. Done.**

Please include a write up of the project and how the costs were developed. Please see the example placed in the folder. V:\Long Beach NY LRR\2013 HSRR for DQC\Appendix C\_Cost Engineering – **Will do. Done.**

Place the MII cost estimate printout at the end of the cost appendix. This information is actually not even necessary. – **Will do. Done**

Where are the results from the ARA? These should be included towards the back of the cost appendix. **Will include main 'Input & Results' printout from ARA. Done**

Where is the annualized cost table? - **Will include printout in the appendix. Was only shown in report initially. Done**

#### CEDEP

“PG 3” - % gross. I would consider a 25% loss instead of 20%. – **Will revise. Done**

Mobilization/Demobilization seems extremely high. Look at the intrasite mob/demob costs. This is extremely high as well, which may be contributing to the high overall cost. I would assume 2 days to mob/demob during an intrasite mob/demob. 1 day to mob and 1 to demob. – **Will revise. Done**

“PG 6” – pipeline used seems to low. The beach is approximately 6 miles long. Therefore I would assume the pipeline will be longer then the 6,000lf currently used. I would assume distance to the shore + shoreline pipe < 12,000lf of pipe. If the total pipeline needed is greater than 12,000lf, then an additional intrasite mob/demob will need to be considered. I see that two intrasite mob/demobs have been considered. – **Agreed. Will revise. Done**

#### MII

Contractor's Markups – Dredging prime contractor's bond seems high at 2%. 1% is more of a reasonable cost for bond for the magnitude of work associated with this job. – **Will revise. Done**

Air Mitigation – Where or how was this cost generated? Please state this in the notes field to explain. – **Will add notes in estimate; value was provided by Environmental on 8 Oct 13. Done**

Cultural Resource Preservation – Where or how was this cost generated? Please state this in the notes field to explain. – **Will add notes to estimate; value was provided by Environmental on 8 Oct 13. Done**

Project Properties – General – Budget year says 2013. Should it be 2014? – **Yes, should be 2014. Will revise. Done**

Project Properties – General – Esc and Eff pricing states July 1<sup>st</sup> 2013. Is this correct or was the pricing completed around the same time the estimate was prepared? – **Will revise; you are correct, pricing was completed with estimate. Done**

Project Properties – Equipment - Check your fuel costs, and adjust accordingly. To be conservative you may want to use the EIA fuel prices for all 3 gas input fields. – **Will revise. Done**

Rehab existing groins – Class B/C unit prices are higher than the unit prices for other Class B/C armor stone. Please review and adjust accordingly. – **Unit costs are higher for this feature because there is some work included to re-grade the existing stones on the groins to allow for a more ideal surface for the new stone to be placed on. Done**

Point Lookout Terminal Groin – Core/Bedding stone is higher than the other core/bedding stones for other groin works. Please review and adjust accordingly. – **There is some removal of existing bedding stone required at the Point Lookout Terminal Groin. This work is included in the same folder as the placement of the new stone, which inflates the unit price of the folder. Done**

#### ARA

Place a date for when the ARA meeting took place. – **Will revise. Done**

The TPCS shows a contingency of 22% for the 30 & 31 accounts. However the “Risk Register” shows that the 30 & 31 accounts have “no impact to cost” and no concerns. I would recommend revisiting the risks for these accounts to get a reasonable contingency. – **Agreed; will revise. Done**

The MII includes two separate accounts, 10 – breakwater & seawalls and 17 – beach replenishment. However the ARA just shows one account. Suggest breaking the ARA into two accounts and possible a couple of features under each account. – **Agreed; will revise. Done**

The PDT discussion for risk concerns for specialty fabrication or equipment does not seem to pertain to the features of work. I also do not see how there would be any risks associated with dredging based on this region and amount of dredging work completed in it. – **Agreed; will revise. Done**

PDT discussion for dredging is inaccurate. A booster pump is being assumed for the dredging process. – **Will revise. Done**

PDT and risks for the stone placement feature of work should be revisited. I assume that production rates for the groin work does not seem to be exact and some risks may be applied to these features of work. – **Agreed; will revise. Done**

#### TPCS

Suggest revising the 30 account costs. Currently you are utilizing 23% of the construction costs as your 30 account cost. Please discuss this with your technical manager (TM) to verify or adjust your percentage. – **Revisited with TM. PED costs were revised to 16%. Done**

Program Year Price Level is 2014Q4. This causes the midpoint of construction for the 01 and 30 accounts to generate a negative escalation. Please clarify and address accordingly. – **Will revise.** **Done**

40% contingency seems extremely high for the 01 account. Please verify this with real estate and address accordingly. – **RE has submitted revised costs with a 20% contingency.** **Done**