




Marsh Building

Finding the Match




U.S. Army Corps of Engineers, NY District
Megan Jadrosich, Project Manager
October 29, 2008



USACE Programs



- **Section 204/207 Beneficial Use of Dredged Material – Regional Sediment Management – 65% Fed 35% NFed**
- **Section 206/1135 Aquatic Ecosystem Restoration**
- **Betterment – 100% NFed**
- **Support for Others – 100% NFed**
- **General Investigations**



Identifying, Planning, and Financing Beneficial Use Projects Using Dredged Material

Beneficial Use Planning Manual



U.S. Environmental Protection Agency, Washington, DC

U.S. Army Corps of Engineers, Washington, DC

The Role of the Federal Standard in the Beneficial Use of Dredged Material from U.S. Army Corps of Engineers New and Maintenance Navigation Projects

Beneficial Uses of Dredged Materials



U.S. Environmental Protection Agency, Wash

U.S. Army Corps of Engineers, Washington, D

JAMAICA BAY MARSH ISLANDS, JAMAICA BAY, NEW YORK
INTEGRATED ECOSYSTEM RESTORATION REPORT
ENVIRONMENTAL ASSESSMENT
AND
FINDING OF NO SIGNIFICANT IMPACT



December 2005



Jamaica Bay Project Support



USACE Marsh Island Restoration Interagency Team:

The Port Authority of New York & New Jersey

New York State Department of Environmental Conservation

New York City Department of Environmental Protection


National Park Service

Native Plant Material:

USDA-Natural Resources Conservation Service

Other Agency Support

Environmental Organizations – Jamaica Bay Task Force





Partnerships



- **Other Funding Sources**
- **Partnership Framework**
- **Local Initiative**



Planning – Construction - Monitoring

Explore Ideas:

The Corporate Wetlands Restoration Partnership

The Cooperative Institute for Coastal and Estuarine Environmental Technology

NOAA - Community-based Restoration Program

NRCS Wetland Reserve Program

Chesapeake Bay Program

Ducks Unlimited

Native Plant Nursery – Volunteer Plantings?



COST




COST per ACRE

COST per HABITAT UNIT





Overview of Ongoing Jamaica Bay Efforts



Jamaica Bay Ecosystem Restoration
CAP Projects (1135)
Marsh Island Sites



Elder's Point – Area Identification



Elders Point East Design

42.69 acres


248,500 cy

750,000 plants

\$16 million


Sand Sources:

1. Rockaway Inlet
Maintenance
2. Ambrose
Navigation Channel
(NY/NJ Harbor 50 ft
Deepening Project)
3. Ambrose Channel:
Private Mining Co.





Elders Point West





Yellow Bar Hassock



EXISTING CONDITIONS



Photo courtesy of NPS







Yellow Bar Preliminary Designs



26.4-acre conceptual design



52-acre conceptual design





Material Source




NY-NJ Harbor Deepening Project

Inlet or Harbor Maintenance

Upland Borrow Site


Offshore Borrow Area?

~~Bay Channels?~~





50 Foot Deepening Project






SEDIMENT SOURCE




Ambrose Channel Dredging





U.S. ARMY

Navigation Channel Survey





Historic Area Remediation Site




BASE PLAN

- NY Mud Dump
- HARS Remediation Areas
- BATHY 1995 NYB**
- 40 - 35 feet
- 45 - 40 feet
- 50 - 45 feet
- 55 - 50 feet
- 60 - 55 feet
- 65 - 60 feet
- 70 - 65 feet
- 75 - 70 feet
- 80 - 75 feet
- 85 - 80 feet
- 90 - 85 feet
- 100 - 90 feet
- 110 - 100 feet
- 120 - 110 feet
- 130 - 120 feet
- 140 - 130 feet
- > 140 feet
- No Data
- NOAA Shoreline




4 0 4 Miles






Environmental Windows



**February/April -
mid-September**



May - July



May & June

When can material be dredged & placed?
Sep-14 through January*

** Depends on dredged material source*





Dredged Material Costs



Approximate Costs for Discussion

HARS Placement	\$8 - \$15/cy
Offshore Borrow Area	>\$12/cy
Anchorage/Ambrose & Elders W. Placement	\$26 - \$41/cy
Pumped from Off-Site Stockpile + (placement of stockpile)	\$35/cy* + (\$9 - \$22 CY)
Upland Sand Source (trucking only – add above costs)	>\$35+ /cy +

INCREMENTAL COST

$$\mathbf{\$26 - \$8 (BASE HARS) = \$18 \text{ cy}}$$

Above costs do not include mob/demob



Material Placement




Off-Site Stockpile

Direct Pump-out

On-Site Stockpile(s)

**Alternative Pump-out
Staging Locations**

**Alternative Pump-Out
Unconfined vs. Confined
(aquabag, coir logs, berm)**





Floyd Bennett Field Staging






**Getting Sand to the Island
Method 1: Stockpile, Re-Slurry and Pump
Across Bay**



Direct Pump From Hopper Dredge





Direct Pump-out from Hopper Dredge to Island was Much More Efficient





Sand Discharge



Any flexibility regarding unconfined pumpout?

October 2006 Aerial

•Photo taken during Sand Pumping Operations,
•During High Tide

Waterfowl Barrie
Cells


Hummocks Relocated
Into Filled Areas

Hummocks
Filled in-situ

Pipeline from
Hopper Dredge



Alternative Pump Out Locations





Site Grading & Drainage




Stockpiled Material?

**Grading by Whom/When:
Dredging Contract or Wetland
Contract**

Settlement Period

***Spartina* Hummock Relocation**

4'



Spartina Hummock



Do not underestimate vertical settlement!




Obtaining geotechnical borings on these marsh islands are often logistically challenging. If no consolidation information is available, contingency for fill volume should reflect that. 40% more fill was needed for the 38 acres of created marsh



Yellow Bar Geotechnical



Yellow Bar Proposed Vibracore Locations



ID	POINT_X	POINT_Y
1	-73.83784945880	40.61185600810
2	-73.83838856400	40.61240304130
3	-73.83847734190	40.61068815670
4	-73.83870568460	40.61140411120
5	-73.83939957330	40.61070280250
6	-73.84059255260	40.61209384860
7	-73.84004551940	40.61217312880
8	-73.84136949820	40.61252196150
9	-73.84086210510	40.61185600810
10	-73.84316122980	40.61323548300
11	-73.84214644380	40.61182429610
12	-73.84404123980	40.61222862490

Legend

-  Vibracore locations - 2/13/08
-  Existing vegetation in project area
-  Existing topography

Map created by GSW, 02/11/08
Data source: NPS existing vegetation

2.5 ft fill





Site Grading



Tidal Creek Plan Form Morphology:

- Self-Adjustments of Creeks Happened 1-3 Month After Placement
- Minimal Adjustments after that (5,7 and 9 months post placement)

MARCH 2007 ————
MAY 2007 - - - - -
JULY 2007 - · - · - ·



Creek 5 –
(Creek was a Modification
to Plans, needed to Drain
Interior Hummock Areas)



Creek 7 – (Creek was a Modification to Plans)



Planting Alternatives



- **No planting (natural recruitment)**
- **Seeding**
- **Plugs (native source?)**
- **Pots (native source?)**
- **Hummocks – Fill around**
- **Hummocks - Transplant**



Instant Marsh or Time for Recruitment?

Capabilities for Monitoring & Adaptive Management



Recruitment & Seeding



No planting (natural recruitment) Seeding

- **Monitoring & Adaptive Management ----
Duration?**
- **Annual output – habitat unit benefits**
- **Seeding – questionable success for
wave/wind intense areas.**
- **Seeding - Agricultural approach; Sexual
Reproduction vs. Vegetative Propagation**
- **Below ground-Above ground biomass**



Native Plant Propagation



What is native?





Planting Plugs



Minimal Equipment – Low Cost



Restoration Success



**Spring
Planting
Window**



Consider wider spacing

Hummocks Left in Place and Filled are Still Struggling (still to wet)



Being
Filled
Sept
2006



April
2007



June
2007



U.S. ARMY

Hummock Transplant




Sequencing



**Need More
Flexibility
with
Planting
Requirments**



Wider Planting Spacing





Filling areas to low marsh grades and Transplanting Hummocks is More Effective than filling around Existing Hummocks



Transplanted:
Sept 06



March
2007

Sept
2007






Existing Hummocks



**YELLOW
BAR**



WEST



- **USACE Guidelines:**
 - 1 % Monitoring
 - 3% Adaptive Mgmt.
 - 5 Years
- **Non-Federal Funding of Monitoring Studies**
- **Responsibility of Adaptive Management**
- **Improve Cost-Efficiency & Output of Survey Efforts**





Contracting Strategies



- **One Contract**
- **Separate Dredging Contract & Small Business Contract for Wetland Build-Out**
- **Cost Reimbursable**
- **Design Build**
- **Turnover for Planting by Others**






U.S. ARMY

Baltimore District – Poplar Island



- Port of Baltimore
- Poplar Island – Chesapeake Bay
- \$340 million
- 40 million cy over 16 years of dredging
- 35,000 ft Containment Dikes
- 1,140 acres
- 570 acres marsh, 570 acres upland habitats
- Success with marsh plugs
- Clamshell Dredge & Pipe from Scow






San Francisco - Hamilton Wetlands



- Port of Oakland
- 950 acres of wetland habitat
- \$62 million
- > 21 million cy
- Supplemental EIS – Evaluating Cost-Effective Technologies for Dredged Material Transport to Restoration Area
- Web page is www.Hamiltonwetlands.org





Louisiana



**Shallow water
“terraces”**



Finding the Match



Value Engineering – February 2008

Industry Meeting – November 2008

Outreach – Marsh Projects Nationwide

Symposium – Monitoring Results



Funding Sources




Partnerships



Alternative Methods

Alternative
Approach to Costly
Marsh Building?





New York District

US Army Corps of Engineers



Thanks to District Team (present & past) & Our Project Partners

Melissa Alvarez - Senior Project Biologist

Bill Slezak, Chief of Harbor Programs Branch

Len Houston, Chief of Environmental Analysis Branch

Gail Woolley, Sheila Rice-McDonnell, & Anthony Schiano – Engineering

Matthew Voisine & Jeff Cusano – Project Biologist & GIS

Jamal Sulayman & Steve Weinberg – Engineering Dredging Team

Shewen Bian & Mark Kucera – Construction Team

Karen Ashton & Steve Couch – Planning

Peter Weppler – Team Leader, Environmental Branch

Presentation also made possible by past USACE Restoration Engineers:

Bethany Bearmore & Kerry Anne Donohue

Visit the District's Project Web Page at:

<http://www.nan.usace.army.mil/project/newyork/factsh/jamaica/index.htm>

Contact Project Manager

Megan.B.Grubb@usace.army.mil



BUILDING STRONG!