

Draft Final Integrated Interim Response
Feasibility Report and Environmental
Assessment

**NEW YORK-NEW JERSEY
HARBOR AND TRIBUTARIES
COASTAL STORM RISK MANAGEMENT
FEASIBILITY STUDY**

**APPENDIX C
COST ENGINEERING**

March 2026

**WALLA WALLA COST ENGINEERING
MANDATORY CENTER OF EXPERTISE**

COST AGENCY TECHNICAL REVIEW

CERTIFICATION STATEMENT

For Project No. 404586

NAN – New York-New Jersey Harbor and Tributaries
Coastal Storm Risk Management
Feasibility Study

The New York-New Jersey Harbor and Tributaries CSRM Feasibility Study, as presented by New York District, has undergone a successful Cost Agency Technical Review (Cost ATR), performed by the Walla Walla District Cost Engineering Mandatory Center of Expertise (Cost MCX) team. The Cost ATR included study of the project scope, report, cost estimates, schedules, escalation, and risk-based contingencies. This certification signifies the products meet the quality standards as prescribed in ER 1110-2-1150 Engineering and Design for Civil Works Projects and ER 1110-2-1302 Civil Works Cost Engineering.

As of March 9, 2026, the Cost MCX certifies the estimated total project cost:

FY26 Project First Cost: \$278,334,000
Fully Funded Amount: \$351,552,000

Cost Certification assumes Efficient Implementation (Funding). It remains the responsibility of the District to correctly reflect these cost values within the Final Report and to implement effective project management controls and implementation procedures including risk management through the period of Federal Participation.



Digitally signed by
Derek Nelson
NELSON.DEREK.DU
ANE.1235538233

**Derek D. Nelson, TCCC
Chief, Cost Engineering MCX
Walla Walla District**

**** TOTAL PROJECT COST SUMMARY ****

PROJECT: New York – New Jersey Harbor and Tributaries Coastal Storm Risk Management Feasibility Study
PROJECT NO: P2 xxxxxx
LOCATION: East Riser, Bergen County, NJ
DISTRICT: New York District
POC: CHIEF, COST ENGINEERING, Anthony Schiano
PREPARED: 2/26/2026

This Estimate reflects the scope and schedule in report:
 Feasibility Submission Report January 2026

| WBS NUMBER | Civil Works Feature & Sub-Feature Description | ESTIMATED COST | | | | PROJECT FIRST COST (Constant Dollar Basis) | | | | TOTAL PROJECT COST (FULLY FUNDED) | | | |
|--|---|----------------|-------------|-----------|-------------|--|------------|-------------|-------------|-----------------------------------|------------|-------------|------------|
| | | COST (\$K) | CONTG (\$K) | CONTG (%) | TOTAL (\$K) | ESC (%) | COST (\$K) | CONTG (\$K) | TOTAL (\$K) | INFLATED (%) | COST (\$K) | CONTG (\$K) | FULL (\$K) |
| 02 | EAST RISER RELOCATIONS | \$14,808 | \$3,998 | 27.0% | \$18,806 | 0.0% | \$14,808 | \$3,998 | \$18,806 | 0.0% | \$14,808 | \$5,140 | \$24,175 |
| 08 | ROADS, RAILROADS & BRIDGES | \$8,237 | \$2,224 | 27.0% | \$10,461 | 0.0% | \$8,237 | \$2,224 | \$10,461 | 0.0% | \$8,237 | \$2,859 | \$13,447 |
| 09 | CHANNELS & CANALS | \$114,020 | \$30,785 | 27.0% | \$144,806 | 0.0% | \$114,020 | \$30,785 | \$144,806 | 0.0% | \$114,020 | \$39,574 | \$186,146 |
| 19 | BUILDINGS, GROUNDS & UTILITIES | \$1,388 | \$375 | 27.0% | \$1,763 | 0.0% | \$1,388 | \$375 | \$1,763 | 0.0% | \$1,388 | \$482 | \$2,266 |
| INITIAL CONSTRUCTION ESTIMATE TOTALS: | | \$138,454 | \$37,382 | | \$175,836 | 0.0% | \$138,454 | \$37,382 | \$175,836 | 0.0% | \$138,454 | \$48,055 | \$226,035 |
| 01 | LANDS AND DAMAGES | \$15,365 | \$7,683 | 50.0% | \$23,048 | 0.0% | \$15,365 | \$7,683 | \$23,048 | 0.0% | \$15,365 | \$8,855 | \$26,564 |
| 30 | PLANNING, ENGINEERING & DESIGN | \$42,444 | \$11,510 | 27.1% | \$53,954 | 0.0% | \$42,444 | \$11,510 | \$53,954 | 0.0% | \$42,444 | \$13,719 | \$64,315 |
| 31 | CONSTRUCTION MANAGEMENT | \$20,076 | \$5,420 | 27.0% | \$25,496 | 0.0% | \$20,076 | \$5,420 | \$25,496 | 0.0% | \$20,076 | \$7,364 | \$34,638 |
| PROJECT COST TOTALS: | | \$216,339 | \$61,995 | 28.7% | \$278,334 | | \$216,339 | \$61,995 | \$278,334 | | \$216,339 | \$77,993 | \$351,552 |

CHIEF, COST ENGINEERING, Anthony Schiano

PROJECT MANAGER, Jamal Sulayman

CHIEF, REAL ESTATE, Helen Luke

CHIEF, PLANNING, Jodi McDonald

CHIEF, ENGINEERING, Encer Shaffer

CHIEF, OPERATIONS, Thomas Creamer

CHIEF, CONSTRUCTION, Richard English

CHIEF, CONTRACTING, Francis Cashman

CHIEF, PM-PB, Joseph Seebode

CHIEF, DPM, Joseph Seebode

ESTIMATED TOTAL INITIAL PROJECT COST: \$175,836

ESTIMATED TOTAL PROJECT COST: \$351,552

35% Cost Share: \$97,416.79
65% Cost Share: \$180,916.89

**** TOTAL PROJECT COST SUMMARY ****

**** CONTRACT COST SUMMARY ****

PROJECT: New York – New Jersey Harbor and Tributaries Coastal Storm Risk Management Feasibility Study - DISTRICT: New York District PREPARED: 2/26/2026
 LOCATION: East Riser, Bergen County, NJ CHIEF, COST ENGINEERING, Anthony Schiano
 This Estimate reflects the scope and schedule in report; Feasibility Submission Report January 2026

| Civil Works Work Breakdown Structure | | ESTIMATED COST | | | | | PROJECT FIRST COST (Constant Dollar Basis) | | | | | TOTAL PROJECT COST (FULLY FUNDED) | | | | | |
|--------------------------------------|---|--|-------------|----------|--------------|---------|--|------------|-------------|---------|-----------|-----------------------------------|--------------|------------|------------|------------|-----------|
| WBS NUMBER | Civil Works Feature & Sub-Feature Description | Estimate Prepared: 1-Jan-26 Effective Price Level: 1-Oct-25 | | | | | Program Year (Budget EC): 2026 Effective Price Level Date: 1 OCT 25 | | | | | Mid-Point Date | INFLATED (%) | COST (\$K) | CNTG (\$K) | FULL (\$K) | |
| | | COST (\$K) | CNTG (\$K) | CNTG (%) | TOTAL (\$K) | ESC (%) | COST (\$K) | CNTG (\$K) | TOTAL (\$K) | ESC (%) | P | | | | | | L |
| 02 | CONTRACT 1 - EAST RISER | \$14,808 | \$3,998 | 27.0% | \$18,806 | 0.0% | \$14,808 | \$3,998 | \$18,806 | 0.0% | \$14,808 | \$3,998 | \$18,806 | 28.5% | \$19,036 | \$5,140 | \$24,175 |
| 08 | RELOCATIONS | \$8,237 | \$2,224 | 27.0% | \$10,461 | 0.0% | \$8,237 | \$2,224 | \$10,461 | 0.0% | \$8,237 | \$2,224 | \$10,461 | 28.5% | \$10,588 | \$2,859 | \$13,447 |
| 09 | ROADS, RAILROADS & BRIDGES | \$114,020 | \$30,785 | 27.0% | \$144,806 | 0.0% | \$114,020 | \$30,785 | \$144,806 | 0.0% | \$114,020 | \$30,785 | \$144,806 | 28.5% | \$146,572 | \$39,574 | \$186,146 |
| 19 | CHANNELS & CANALS | \$1,388 | \$375 | 27.0% | \$1,763 | 0.0% | \$1,388 | \$375 | \$1,763 | 0.0% | \$1,388 | \$375 | \$1,763 | 28.5% | \$1,784 | \$482 | \$2,266 |
| | BUILDINGS, GROUNDS & UTILITIES | \$138,454 | \$37,382 | 27.0% | \$175,836 | | \$138,454 | \$37,382 | \$175,836 | | \$138,454 | \$37,382 | \$175,836 | | \$177,980 | \$48,055 | \$226,035 |
| 01 | LANDS AND DAMAGES | \$15,365 | \$7,682,500 | 50.0% | \$23,047,500 | 0.0% | \$15,365 | \$7,683 | \$23,048 | 0.0% | \$15,365 | \$7,683 | \$23,048 | 15.3% | \$17,709 | \$8,855 | \$26,564 |
| 30 | PLANNING, ENGINEERING & DESIGN | \$3,461 | \$935 | 27.0% | \$4,396 | 0.0% | \$3,461 | \$935 | \$4,396 | 0.0% | \$3,461 | \$935 | \$4,396 | 10.5% | \$3,826 | \$1,033 | \$4,859 |
| 2.5% | Project Management | \$1,385 | \$374 | 27.0% | \$1,758 | 0.0% | \$1,385 | \$374 | \$1,758 | 0.0% | \$1,385 | \$374 | \$1,758 | 10.5% | \$1,530 | \$413 | \$1,943 |
| 1.0% | Planning & Environmental Compliance | \$20,768 | \$5,607 | 27.0% | \$26,375 | 0.0% | \$20,768 | \$5,607 | \$26,375 | 0.0% | \$20,768 | \$5,607 | \$26,375 | 10.5% | \$22,955 | \$6,198 | \$29,152 |
| 15.0% | Engineering & Design | \$1,385 | \$374 | 27.0% | \$1,758 | 0.0% | \$1,385 | \$374 | \$1,758 | 0.0% | \$1,385 | \$374 | \$1,758 | 10.5% | \$1,530 | \$413 | \$1,943 |
| 1.0% | Reviews, ATRs, IEPs, VE | \$1,385 | \$374 | 27.0% | \$1,758 | 0.0% | \$1,385 | \$374 | \$1,758 | 0.0% | \$1,385 | \$374 | \$1,758 | 10.5% | \$1,530 | \$413 | \$1,943 |
| 1.0% | Life Cycle Updates (cost, schedule, risks) | \$1,385 | \$374 | 27.0% | \$1,758 | 0.0% | \$1,385 | \$374 | \$1,758 | 0.0% | \$1,385 | \$374 | \$1,758 | 10.5% | \$1,530 | \$413 | \$1,943 |
| 3.0% | Contracting & Reprographics | \$4,154 | \$1,121 | 27.0% | \$5,275 | 0.0% | \$4,154 | \$1,121 | \$5,275 | 0.0% | \$4,154 | \$1,121 | \$5,275 | 35.9% | \$5,643 | \$1,524 | \$7,167 |
| 2.0% | Engineering During Construction | \$2,769 | \$748 | 27.0% | \$3,517 | 0.0% | \$2,769 | \$748 | \$3,517 | 0.0% | \$2,769 | \$748 | \$3,517 | 35.9% | \$3,762 | \$1,016 | \$4,778 |
| 3.0% | Planning During Construction | \$4,154 | \$1,121 | 27.0% | \$5,275 | 0.0% | \$4,154 | \$1,121 | \$5,275 | 0.0% | \$4,154 | \$1,121 | \$5,275 | 56.6% | \$6,505 | \$1,756 | \$8,261 |
| 3.0% | Adaptive Management & Monitoring | \$1,385 | \$374 | 27.0% | \$1,758 | 0.0% | \$1,385 | \$374 | \$1,758 | 0.0% | \$1,385 | \$374 | \$1,758 | 10.5% | \$1,530 | \$413 | \$1,943 |
| 1.0% | Project Operations | \$216 | \$108 | 50.0% | \$324 | 0.0% | \$216 | \$108 | \$324 | 0.0% | \$216 | \$108 | \$324 | 17.7% | \$254 | \$127 | \$381 |
| | Real Estate (All Federal Labor) | | | | | | | | | | | | | | | | |
| 31 | CONSTRUCTION MANAGEMENT | \$13,845 | \$3,738 | 27.0% | \$17,584 | 0.0% | \$13,845 | \$3,738 | \$17,584 | 0.0% | \$13,845 | \$3,738 | \$17,584 | 35.9% | \$18,810 | \$5,079 | \$23,888 |
| 10.0% | Construction Management | \$2,769 | \$748 | 27.0% | \$3,517 | 0.0% | \$2,769 | \$748 | \$3,517 | 0.0% | \$2,769 | \$748 | \$3,517 | 35.9% | \$3,762 | \$1,016 | \$4,778 |
| 2.0% | Project Operation: | \$3,461 | \$935 | 27.0% | \$4,396 | 0.0% | \$3,461 | \$935 | \$4,396 | 0.0% | \$3,461 | \$935 | \$4,396 | 35.9% | \$4,702 | \$1,270 | \$5,972 |
| 2.5% | Project Management | | | | | | | | | | | | | | | | |
| | CONTRACT COST TOTALS: | \$216,339 | \$61,995 | 28.66% | \$278,334 | | \$216,339 | \$61,995 | \$278,334 | | \$216,339 | \$61,995 | \$278,334 | | \$273,559 | \$77,983 | \$351,552 |

U.S. Army Corps of Engineers (USACE)

DESIGN MATURITY DETERMINATION FOR COST CERTIFICATION

For use of this form, see ER 1110-2-1302; the Proponent agency is CEEC

Purpose: The purpose of this form is to determine design maturity for cost certification.

SECTION I: PROJECT INFORMATION

DATE: 3/9/26

P2 Designation/Project Name: 404586/NYNJHATS Actionable Elements- East Rise

The Chief of Engineering is responsible for the technical content and engineering sufficiency for all engineering products produced by the command. As such, I have performed the Management Control Evaluation per Engineer Regulation (ER) 1110-2-1150, Engineering and Design for Civil Works Projects, Appendix H, Internal Management Control Review Checklist.

1. The current design DOES NOT require HQ approval (i.e., engineering waivers), requiring a deviation from mandatory requirements and mandatory standards, as defined in ERs, Engineer Manuals (EMs), Engineer Technical Letters, and Engineer Circulars.

2. The current hydrology and hydraulics modeling is at 90 % design maturity, per reference (g) below.

3. The current geotechnical data and subsurface investigations are at 90 % design maturity, per reference (g) below. Subsurface investigations shall also include investigations of potential borrow and spoil areas.

4. The current survey data is at 90 % design maturity, per reference (g) below.

5. Other major technical and/or scope assumptions and risks include the following, which will be refined as the design progresses:

6. The aggregate for all features is 90 % design maturity. Therefore, per ER 1110-2-1302, Civil Works Cost Engineering, I certify that the design deliverables used to generate the cost products for this project and the estimate meet the requirements for a CLASS 2 estimate, as per reference (a) below. Design risks, impacts, and remaining efforts are summarized on page 2.

7. The total project baseline schedule for this project is 40 months. This schedule was coordinated with the Project Manager, Project Delivery Team, and Non-Federal Sponsor, and takes into consideration the project constraints, including district execution capacity, capability of providing real estate in a timely fashion, and cost-share budget requirements, along with the market conditions, including industry capability to execute the project.

8. Considering risks and assumptions noted above, along with all other concerns documented in the Risk Register, the Cost and Schedule Risk Analysis has developed a contingency of 27 % at the 80 % confidence level for the defined project scope.

TITLE: CHIEF OF ENGINEERING



NAME: Encer Shaffer, P.E.

OFFICE SYMBOL: CENAN-EN

DATE: 3/11/26

SIGNATURE:

SECTION II: REMAINING WORK

If an engineering waiver is required, list the risks and remaining design work needed to mitigate this issue in the current design. Identify remaining effort to complete the design required for 100% design.

Identify remaining effort to complete geotechnical design effort required for 100% design. List the risks and cost and schedule impacts needed to mitigate this issue in the current design.

The geotechnical design is based on borings at each bridge site and at selected locations along the channel. The design meets required stability factors of safety. It is anticipated that the design will need to be verified relative to any revisions in USACE, DOT or other guidance. Additional borings may be needed.

Identify remaining effort required to complete H&H required for 100% design. List the risks and cost and schedule impacts needed to mitigate this issue in the current design.

The H&H data is complete based on the current design. It is anticipated that some additional analysis will be required to comply with State on NJ permit requirements and to incorporate any minor changes in existing conditions or project design.

Identify remaining effort needed to complete survey data required for 100% design. List the risks and cost and schedule impacts needed to mitigate this issue in the current design.

The survey has been completed to a 100% design. Given the delay until the start of construction, updated survey will be needed to reflect changes in nearby development and to calculate channel excavation quantities. Survey data is from 2019. Additional survey may be needed after site visit and evaluation.

If the project is anticipated to be executed in parts, provide a design assessment (percent complete) of each part/phase below.

SECTION III: REFERENCES

- a. ER 1110-2-1302 – Civil Works Cost Engineering
- b. CECW-EC (CEEC) memorandum dated 05-June-2023 MFR, Guidance on Cost Engineering Products update for Civil Works Projects in accordance with Engineer Regulation 1110-2-1302 – Civil Works Cost Engineering
- c. ER 1165-2-217 – Civil Works Quality and Review Policy
- d. ER 1110-2-1150 – Engineering and Design for Civil Works Projects
- e. ER 1110-345-700 – Design Analysis, Drawings and Specifications
- f. EM 5-1-11 – Project Delivery Business Process (PDBP)
- g. Engineering and Construction Bulletin (ECB) 2023-9 – Civil Works Design Milestone Checklists

SECTION IV: INSTRUCTIONS

Page 1 – Design Date: Use the drop-down menu to populate the date of the design.

P2 Designation/Project Information: Enter the P2 Project number and Project name.

Paragraph 1 – Engineering Waivers: Use the drop-down menu to populate this field with either “Does,” or “Does not.” If an engineering waiver is needed, or anticipated to be needed, provide the specific waiver required for the Project. A waiver is any deviation from current mandatory standards, as indicated.

Paragraph 2 – Hydrology and Hydraulics: Populate this field with the percent of design maturity.

Paragraph 3 – Geotechnical Information: Populate this field with the percent of design maturity.

Paragraph 4 – Survey Data: Populate this field with the percent of design maturity.

Paragraph 5 – Other Technical Assumptions and/or Scope: Enter any other major technical assumptions or scope assumptions here. Only include assumptions that pertain to design. Template discussion fields are provided as a courtesy. Please include additional pages as an attachment as necessary.

Paragraph 6 – Aggregate for All Features: Populate this field with the percent of design maturity. Use the dropdown menu to choose which class of estimate is met by the design deliverables.

Paragraph 7 – Total Project Baseline Schedule: Populate this field with the total project baseline schedule for the project in months.

Paragraph 8 – Contingency and Confidence Level for the Defined Project Scope: Populate these fields with the contingency percentage and confidence level percentage for the defined project scope.

Signature: Print the name and provide the title and signature for the District’s Chief of Engineering. This authority cannot be delegated; however, the Deputy Chief of Engineering and Design may sign the form in the absence of the Chief of Engineering. All fillable fields must be populated (use N/A if not applicable) in order for the document to be signed.

Page 2 – Remaining Work: Identify the current baseline design assumptions and the remaining design effort and risks to complete 100% design for the authorized project. If the project is to be broken into parts or phases, provide details on the aggregate design level of each phase and anticipated timeline for completion.

TABLE OF CONTENTS

| | | |
|------|---|----|
| 1. | INTRODUCTION | 3 |
| 1.1. | Objective..... | 3 |
| 1.2. | Basis of Cost..... | 4 |
| 1.3. | General Description of the Project Features | 6 |
| 2. | WORK BREAKDOWN STRUCTURE..... | 7 |
| 2.1. | Initial Construction Estimate..... | 7 |
| 3. | INTEREST DURING CONSTRUCTION AND O&M | 8 |
| 3.1. | Interest During Construction | 8 |
| 3.2. | Operation and Maintenance..... | 8 |
| 3.3. | Annualized Cost..... | 7 |
| 4. | ESTIMATED DESIGN AND CONSTRUCTION SCHEDULE..... | 8 |
| 5. | CONTINGENCIES | 9 |
| 6. | FIRST COST TABLE | 10 |
| 7. | TOTAL PROJECT COST SUMMARY | 11 |

LIST OF FIGURES

| | | |
|-------------|--|---|
| Figure 1-1. | East Riser Actionable Element General Setting..... | 5 |
|-------------|--|---|

LIST OF TABLES

| | | |
|------------|---|----|
| Table 3-1: | Annualized Cost..... | 8 |
| Table 4-1: | East Riser Design and Construction Schedule | 8 |
| Table 4-2: | East Riser Construction Duration | 9 |
| Table 5-1: | Contingencies | 10 |
| Table 6-1: | Project First Cost Table..... | 10 |

LIST OF ATTACHMENTS

ATTACHMENT C-3A – TOTAL PROJECT COST SUMMARY (TPCS)

ATTACHMENT C-3B – EAST RISER MII REPORT

1. INTRODUCTION

1.1. Objective

The New York District (NYD) Corps of Engineers is conducting a feasibility level study to evaluate coastal storm risk management (CSRM) on the New York New Jersey Harbors and Tributaries Study (NYNJHAT) area.

At the time of the release of the Draft Integrated Interim FR/EA in July 2025, the TSP chosen for advancement was Alternative C, the Total Net Benefits Plan. This alternative included the Harlem River, Oakwood Beach, and East Riser Actionable Elements. However, prior to release of the Draft Integrated Interim Response FR/EA, the study team, which includes the New York District, NJDEP, NYSDEC, NYCDEP, and NYSDOS confirmed that the Harlem River Actionable Element would not be sufficiently developed or detailed to support USACE design maturity requirements within the timeline for inclusion in a Chief of Engineer's Report, which could be considered by Congress for authorization in a potential WRDA of 2026. Noting this with the need for more robust and meaningful public engagement, as well as the additional engineering analyses needed to meet the USACE engineering design requirement standards, the study team released the Draft Integrated Interim Response FR/EA in July of 2025 with the caveat that the Harlem River Actionable Element would be deferred to a later iteration of Actionable Elements to consider, subject to the future availability of funds.

The other Actionable Elements, East Riser and Oakwood Beach, have since been optimized after having undergone public review and coordination. These Actionable Elements and the analyses done to advance their associated engineering designs are outlined within this Interim Response Report. Specifically, the East Riser Actionable Element has been sufficiently studied and is ready for potential Congressional consideration, to be authorized in WRDA 2026 as a Recommended Plan, Alternative B.

The Oakwood Beach Actionable Element was initially justified as part of Alternative C, by considering a comprehensive benefits analysis, in which this site specifically maximized benefits within the EQ and OSE accounts, and had positive NED account benefits. While USACE recognizes the benefit this Actionable Element Project would provide and the public support for this element as a Nature-Based Solution, as the study team analyzed Oakwood Beach further, it became evident that it would not be ready for inclusion in the final report as the

minimum design maturity would not have been achieved nor would the project cost estimates been developed to meet acceptable requirements. Therefore, USACE is recommending deferral of the Oakwood Beach Actionable Element until such time that the necessary information can be further developed to meet current regulations and policy. Accordingly, the Oakwood Beach Actionable Element has been removed as part of the NY District's Recommended Plan for advancement through a Chief of Engineer's Report, for Congressional authorization within a potential WRDA 2026.

After careful evaluation of the alternatives and their tradeoffs, and consideration of the optimization done since the July 2025 Draft Report the study team selected Alternative B, East Riser Actionable Element, as the Recommended Plan. East Riser also considers multiple flood drivers as requested by the State of New Jersey through Section 8106(a) of WRDA 2022 through the confluence of coastal and riverine flood drivers.

The Recommended Plan includes channel modifications, two bridge culvert replacements, and a railroad bridge replacement on East Riser Ditch Channel in Carlstadt and Moonachie, New Jersey. Channel modifications, more specifically, include widening and deepening of the East Riser Ditch Channel, bank stabilization, and replanting of vegetation

This appendix includes the cost estimates and construction schedules developed for East Riser, to achieve a Class 3 cost estimate per United States Army Corps of Engineers (USACE) Engineer Regulation (ER) 1110-2-1302 and Engineering and Construction Bulletin (ECB) 2023-9. This report supports evaluation of technical feasibility and informs USACE participation consistent with the NYNJHATS Main Report.

1.2. Basis of Cost

The construction cost estimate was developed in MCACES, Second Generation (MII) using the appropriate Work Breakdown Structure (WBS) and based on current estimated quantities provided by the Architect/Engineer. The cost estimate was developed from these quantities using cost resources such as RSMMeans, historical data from similar construction features, and MII Cost Libraries. The contingencies were developed based on input to the Cost Schedule Risk Analysis (CSRA) (template provided by the Cost Mandatory Center of Expertise, MCX, Walla Walla District). These contingencies were applied to the construction cost estimates to develop the Total Project First Cost. The construction duration for East Riser was estimated at 40 months or 1121 days.

1.3. General Description of the Project Features

Figure 1-1 on the following page shows the major components and location of East Riser. The East Riser Actionable Element includes a proposal of channel modifications, three culvert replacements, and a railroad bridge replacement on East Riser Ditch Channel. Channel modifications more specifically include widening and deepening of the East Riser Ditch Channel, bank stabilization, and replanting of vegetation.




Figure 1-1. East Riser Actionable Element General Setting

2. WORK BREAKDOWN STRUCTURE

2.1. Initial Construction Estimate

2.1.1. 01 – Lands and Damages

This account covers Real Estate costs for Construction. The initial estimate for real estate costs was developed by USACE NAN Real Estate and accounts for costs related to land acquisition, land surveys, appraisals, titles services & closing costs.

2.1.2. 02 – Relocations

This account covers the relocation of water, gas, and other miscellaneous utilities throughout the project area including utility relocations for the replacement of the Norfolk-Southern rail bridge, Armor Avenue roadway bridge, and West Commercial Avenue roadway bridge.

2.1.3. 08 – Roads, Railroads, & Bridges

This account covers the replacement of the Norfolk-Southern rail bridge, Armor Avenue roadway bridge, and West Commercial Avenue roadway bridge. The bridge replacement activities include temporary cofferdams and dewatering, demolition, new abutments, superstructure steel or prestressed concrete slab beams, rail track or concrete bridge deck, and other miscellaneous rail and roadway elements.

2.1.4. 09 – Channels & Canals

This account covers activities related to the channel improvements. The channel improvements consist of bank stabilization, the widening and deepening of the East Riser Ditch Channel, and the replanting of vegetation along about 4,150 feet of the lower reach of the channel.

2.1.5. 19 – Buildings, Grounds & Utilities

This account covers activities related to the construction of a new stormwater sewer utility.

2.1.6. 30 – Planning, Engineering and Design (PED)

The cost was developed for all activities associated with the planning, engineering and design effort. The cost for this account includes the preparation of Design Documentation Reports, plans, and specifications for East Riser and engineering support during construction through project completion. It includes all the in-house labor based upon work-hour requirements, material and facility costs, travel, and overhead.

2.1.7. 31 – Construction Management

The cost was developed for all construction management activities from pre-award requirements through final contract closeout. This cost includes the in-house labor based upon work-hour requirements, materials, facility costs, support contracts, travel and overhead. The cost was developed based on the input from the construction division in accordance with the Civil Works Breakdown Structure (CWBS) and includes, but is not limited to, anticipated items such as the salaries of the resident engineer and staff, surveyors, inspectors, drafters, clerical, and custodial personnel; operation, maintenance and fixed charges for transportation and for other field equipment; field supplies; construction management, general construction supervision; and project office administration, distributive cost of area office and general overhead charged to the project.

3. INTEREST DURING CONSTRUCTION AND O&M

3.1. Interest During Construction

Interest during construction (IDC) is the amount of interest the construction cost would earn were it invested from the beginning of construction until the accumulation of benefits begins. IDC cost has been added to the project cost to determine investment cost. Average annual cost was determined based on investment cost, which includes IDC. The pre-base year costs were estimated using the Federal interest rate of 3.25 percent.

3.2. Operation and Maintenance

The Operation and Maintenance (O&M) cost was estimated to represent the anticipated annual costs necessary to maintain the project at full operating efficiency throughout the project life. Following completion of the project, operation and maintenance of project facilities would be the responsibility of the non-Federal sponsor in accordance with Federal regulations and operations manual.

3.3. Annualized Cost

Annual costs are based on an economic period of analysis of 50 years and an interest rate of 3.25%. The annual costs include the annualized investment cost along with annual operation and maintenance cost. A detailed breakdown of annual costs for East Riser is presented in Table 3-1 on the following page.

**Table 3-1: Annualized Cost
East Riser O&M**

| | | |
|--|----|------------------|
| First Cost | \$ | 175,835,310 |
| Sunk Cost | \$ | - |
| Investment Cost | | |
| Interest During Construction ^(a) | \$ | 9,456,207 |
| Total Investment Cost: | \$ | 185,291,517 |
| Annual Costs | | |
| Annualized Investment Cost ^(b) | \$ | 7,546,974 |
| Annualized Operation & Maintenance Cost ^(c) | \$ | 879,176.55 |
| Total Annual Cost* | \$ | 8,426,151 |

*March 2026 Price Level

- (a) Based on 40 months of construction @ 3.25% (IDC, E&D, RE and Sunk costs calculated separately and included in this total)
- (b) Annualized investment cost only includes the remaining features. For annualized investment cost with the sunk cost, please see the economic appendix. I = 3.25% and n = 50 yrs
- (c) Assume 0.5% of total Construction Cost base on historical data.

4. ESTIMATED DESIGN AND CONSTRUCTION SCHEDULE

The estimate is based on the entire contract awarded to a single prime contractor. The estimated design and construction schedule is presented in Table 4-1. The estimated construction duration is presented in Table 4-2. A construction duration contingency will be added to the values summarized through the CSRA.

Table 4-1: East Riser Design and Construction Schedule

| Phase | Estimated Start | Estimated End |
|----------------------------------|-----------------|---------------|
| PED | Q1 2027 | Q2 2029 |
| Solicit/Award/RE Acquisitions | Q2 2029 | Q3 2033 |
| Construction | Q3 2033 | Q4 2037 |
| Monitoring & Adaptive Management | Q4 2037 | Q4 2042 |

Table 4-2: East Riser Construction Duration

| Description | Duration (days) |
|--|-----------------------|
| Mobilization and Site Preparation | 38 |
| Upgrade R x R, Amor Ave, and West Commercial Ave Bridges | 392 |
| Reach 1 Channel Improvements | 255 |
| Reach 2 Channel Improvements | 163 |
| Reach 3 Channel Improvements | 235 |
| Demobilization | 38 |
| Total Duration: | 1121 Days (4.3 years) |

5. CONTINGENCIES

As stated in ER 1110-2-1302, the goal in contingency development is to identify the uncertainty associated with an item of work or task to an acceptable degree of confidence. Consideration must be given to the detail available at each stage of planning, design, or construction for which a cost estimate is being prepared. Contingency may vary throughout the cost estimate and could constitute a significant portion of the overall costs when data or design details are unavailable. Final contingency development and assessment of the potential for cost growth is included in this cost estimate. To develop the Total Project First Cost, contingencies developed in the CSRA were applied. The construction cost contingency developed per CSRA for East Riser is shown in Table 5-1: Contingencies in the following page.

Table 5-1: Contingencies

| Element | Contingency Factor |
|---------------------------------------|--------------------|
| 02 Relocation | 27.00% |
| 08 Roads, Railroads & Bridges | 27.00% |
| 09 Channels & Canals | 27.00% |
| 19 Buildings, Grounds & Utilities | 27.00% |
| Total Construction Contingency | 27.00% |
| 01 Lands & Damages | 50.00% |
| 30 Planning, Engineering, and Design | 27.00% |
| 31 Construction Management | 27.00% |

6. FIRST COST TABLE

The First Cost table for East Riser is presented in Table 6-1.

Table 6-1: Project First Cost Table

| CW WBS | Subtotal | Cont. % | Total Cost |
|--------------------------------------|----------------------|---------------|----------------------|
| East Riser | | | |
| 02 Relocations | \$14,808,000 | 27% | \$18,806,000 |
| 08 Roads, Railroads & Bridges | \$8,237,000 | 27% | \$10,461,000 |
| 09 Channels & Canals | \$114,020,000 | 27% | \$144,805,000 |
| 19 Buildings, Grounds & Utilities | \$1,388,000 | 27% | \$1,763,000 |
| Construction Cost Subtotal | \$138,453,000 | 27% | \$175,835,000 |
| 01 Lands & Damages | \$15,365,000 | 50% | \$23,048,000 |
| 30 Planning, Engineering, and Design | \$42,444,000 | 27% | \$53,954,000 |
| 31 Construction Management | \$20,076,000 | 27% | \$25,496,000 |
| Project Costs Total | \$216,338,000 | 28.66% | \$278,333,000 |

7. TOTAL PROJECT COST SUMMARY

The Total Project Cost Summary (TPCS) considers an estimation of future inflation costs that are expected to occur over the duration of construction of the project. The TPCS, presented in Attachment C-3A represents the estimated “at complete cost of expenditures” for East Riser. The Total Project Cost is the constant dollar cost fully funded with escalation to the estimated midpoint of construction and is the cost estimate used in project partnership agreements; the Total Project Cost is estimated to be \$351,551,000 with the midpoint of construction being 2035Q4.

ATTACHMENT C-3A – TOTAL PROJECT COST SUMMARY (TPCS)

**** TOTAL PROJECT COST SUMMARY ****

Printed:3/24/2026
Page 2 of 4

*** CONTRACT COST SUMMARY ***

PROJECT: New York – New Jersey Harbor and Tributaries Coastal Storm Risk Management Feasibility Study -
LOCATION: East Riser, Bergen County, NJ
This Estimate reflects the scope and schedule in report

DISTRICT: New York District
POC: CHIEF, COST ENGINEERING, Anthony Schiano

PREPARED: 2/26/2026

Feasibility Submission Report January 2026

| Civil Works Work Breakdown Structure | | ESTIMATED COST | | | | PROJECT FIRST COST (Constant Dollar Basis) | | | | TOTAL PROJECT COST (FULLY FUNDED) | | | | |
|--------------------------------------|--|--|-----------------|----------------------|------------------|--|------------------|-----------------|------------------|-----------------------------------|-----------------|------------------|-----------------|------------------|
| WBS NUMBER | Civil Works Feature & Sub-Feature Description | Estimate Prepared: Effective Price Level: | | 1-Jan-26 1-Oct-25 | | Program Year (Budget EC): Effective Price Level Date: | | | | Mid-Point Date | INFLATED (%) | COST (\$K) | QNTG (\$K) | FULL (\$K) |
| | | COST (\$K) | CNTG (\$K) | CNTG (%) | TOTAL (\$K) | ESC (%) | COST (\$K) | CNTG (\$K) | TOTAL (\$K) | | | | | |
| A | B | C | D | E | F | G | H | I | J | P | L | M | N | O |
| CONTRACT 1 - EAST RISER | | | | | | | | | | | | | | |
| 02 | RELOCATIONS | \$14,808 | \$3,998 | 27.0% | \$18,806 | 0.0% | \$14,808 | \$3,998 | \$18,806 | 2035Q4 | 28.5% | \$19,036 | \$5,140 | \$24,175 |
| 08 | ROADS, RAILROADS & BRIDGES | \$8,237 | \$2,224 | 27.0% | \$10,461 | 0.0% | \$8,237 | \$2,224 | \$10,461 | 2035Q4 | 28.5% | \$10,588 | \$2,859 | \$13,447 |
| 09 | CHANNELS & CANALS | \$114,020 | \$30,785 | 27.0% | \$144,805 | 0.0% | \$114,020 | \$30,785 | \$144,805 | 2035Q4 | 28.5% | \$146,571 | \$39,574 | \$186,146 |
| 19 | BUILDINGS, GROUNDS & UTILITIES | \$1,388 | \$375 | 27.0% | \$1,763 | 0.0% | \$1,388 | \$375 | \$1,763 | 2035Q4 | 28.5% | \$1,784 | \$482 | \$2,266 |
| CONSTRUCTION ESTIMATE TOTALS: | | \$138,453 | \$37,382 | 27.0% | \$175,835 | | \$138,453 | \$37,382 | \$175,835 | | | \$177,980 | \$48,054 | \$226,034 |
| 01 | LANDS AND DAMAGES | \$15,365 | \$7,882,500 | 50.0% | \$23,047,500 | 0.0% | \$15,365 | \$7,883 | \$23,048 | 2031Q3 | 15.3% | \$17,709 | \$8,855 | \$26,564 |
| 30 | PLANNING, ENGINEERING & DESIGN | | | | | | | | | | | | | |
| 2.5% | Project Management | \$3,461 | \$935 | 27.0% | \$4,396 | 0.0% | \$3,461 | \$935 | \$4,396 | 2029Q2 | 10.5% | \$3,826 | \$1,033 | \$4,859 |
| 1.0% | Planning & Environmental Compliance | \$1,385 | \$374 | 27.0% | \$1,758 | 0.0% | \$1,385 | \$374 | \$1,758 | 2029Q2 | 10.5% | \$1,530 | \$413 | \$1,943 |
| 15.0% | Engineering & Design | \$20,768 | \$5,607 | 27.0% | \$26,375 | 0.0% | \$20,768 | \$5,607 | \$26,375 | 2029Q2 | 10.5% | \$22,955 | \$6,198 | \$29,152 |
| 1.0% | Reviews, ATRs, IEPs, VE | \$1,385 | \$374 | 27.0% | \$1,758 | 0.0% | \$1,385 | \$374 | \$1,758 | 2029Q2 | 10.5% | \$1,530 | \$413 | \$1,943 |
| 1.0% | Life Cycle Updates (cost, schedule, risks) | \$1,385 | \$374 | 27.0% | \$1,758 | 0.0% | \$1,385 | \$374 | \$1,758 | 2029Q2 | 10.5% | \$1,530 | \$413 | \$1,943 |
| 1.0% | Contracting & Reprographics | \$1,385 | \$374 | 27.0% | \$1,758 | 0.0% | \$1,385 | \$374 | \$1,758 | 2029Q2 | 10.5% | \$1,530 | \$413 | \$1,943 |
| 3.0% | Engineering During Construction | \$4,154 | \$1,121 | 27.0% | \$5,275 | 0.0% | \$4,154 | \$1,121 | \$5,275 | 2035Q4 | 35.9% | \$5,643 | \$1,524 | \$7,167 |
| 2.0% | Planning During Construction | \$2,769 | \$748 | 27.0% | \$3,517 | 0.0% | \$2,769 | \$748 | \$3,517 | 2035Q4 | 35.9% | \$3,782 | \$1,016 | \$4,778 |
| 3.0% | Adaptive Management & Monitoring | \$4,154 | \$1,121 | 27.0% | \$5,275 | 0.0% | \$4,154 | \$1,121 | \$5,275 | 2040Q2 | 58.6% | \$8,505 | \$1,756 | \$10,261 |
| 1.0% | Project Operations | \$1,385 | \$374 | 27.0% | \$1,758 | 0.0% | \$1,385 | \$374 | \$1,758 | 2029Q2 | 10.5% | \$1,530 | \$413 | \$1,943 |
| | Real Estate (All Federal Labor) | \$216 | \$108 | 50.0% | \$324 | 0.0% | \$216 | \$108 | \$324 | 2031Q2 | 17.7% | \$254 | \$127 | \$381 |
| 31 | CONSTRUCTION MANAGEMENT | | | | | | | | | | | | | |
| 10.0% | Construction Management | \$13,845 | \$3,738 | 27.0% | \$17,584 | 0.0% | \$13,845 | \$3,738 | \$17,584 | 2035Q4 | 35.9% | \$18,810 | \$5,079 | \$23,888 |
| 2.0% | Project Operation: | \$2,769 | \$748 | 27.0% | \$3,517 | 0.0% | \$2,769 | \$748 | \$3,517 | 2035Q4 | 35.9% | \$3,782 | \$1,016 | \$4,778 |
| 2.5% | Project Management | \$3,461 | \$935 | 27.0% | \$4,396 | 0.0% | \$3,461 | \$935 | \$4,396 | 2035Q4 | 35.9% | \$4,702 | \$1,270 | \$5,972 |
| CONTRACT COST TOTALS: | | \$216,338 | \$61,995 | 28.66% | \$278,333 | | \$216,338 | \$61,995 | \$278,333 | | | \$273,559 | \$77,992 | \$351,551 |



ATTACHMENT C-3B – EAST RISER MII REPORT

Print Date Tue 24 March 2026
 Eff. Date 1/12/2026

CUI
 U.S. Army Corps of Engineers
 Project : 13372.106.EastRiser.OPCC.30PercentDesign

Time 11:17:54

Overview Page 1

| Description | UOM | Quantity | DirectLabor | DirectEQ | DirectMatl | ProjectCost |
|--|-----------|-------------|------------------------|-----------------------|------------------------|-------------------------|
| Overview | | | 26,672,419.61 | 9,633,693.05 | 39,419,644.96 | 137,533,531.26 |
| | | | <i>26,672,419.6072</i> | <i>9,633,693.0525</i> | <i>39,419,644.9602</i> | <i>137,533,531.2626</i> |
| East Riser OPCC | EA | 1.00 | 26,672,419.61 | 9,633,693.05 | 39,419,644.96 | 137,533,531.26 |
| | | | <i>2,990,820.8033</i> | <i>518,623.4642</i> | <i>3,810,263.0321</i> | <i>13,888,242.5940</i> |
| 02 Relocations | EA | 1.00 | 2,990,820.80 | 518,623.46 | 3,810,263.03 | 13,888,242.59 |
| | | | <i>773,609.3056</i> | <i>219,221.5534</i> | <i>3,608,403.5821</i> | <i>8,236,879.2053</i> |
| 08 Roads, Railroads, & Bridges | EA | 1.00 | 773,609.31 | 219,221.55 | 3,608,403.58 | 8,236,879.21 |
| | | | <i>22,783,462.4192</i> | <i>8,848,315.1927</i> | <i>31,638,880.8057</i> | <i>114,020,279.3721</i> |
| 09 Channels & Canals | EA | 1.00 | 22,783,462.42 | 8,848,315.19 | 31,638,880.81 | 114,020,279.37 |
| | | | <i>124,527.0792</i> | <i>47,532.8423</i> | <i>362,097.5403</i> | <i>1,388,130.0913</i> |
| 19 Building, Grounds, & Utilities | EA | 1.00 | 124,527.08 | 47,532.84 | 362,097.54 | 1,388,130.09 |

*Note: There are \$920,000 of additional costs for Account 02 Relocations in Real Estate Costs that are not included in the estimate shown here.

