

What does the Long Beach Project include?

The Project details are provided below

m110 ft berm 49 ft NAVD88	Point Lookout:
35,000 If *	Seach fill length
4,720,000 cy	Volume of initial fill
1,770,000 cy	Volume of renourishment
every 5 years	Interval of renourishment

Mickerson Beach: existing berm

Long Beach and Lido Beach: 190 ft berm** \$4 A Lido Beach: 190 ft berm**

\$4 A Lido Beach: 190 ft NAVD88 to +7 ft NAVD88

Dune Crest 25 It at +14 It NAVD88

Existing groins rehabilitated

A mew groins

A mew groins

Initial construction cost \$177,876,000 Renourishment costs / cycle \$38,394,000

Annual costs \$13,938,000 Annual benefits \$27,664,000 Benefit to cost ratio

Initial Construction:
Federal(100%) \$177,876,000
Non-Federal (0%) \$0

Renourishment (per cycle) \$24,956,000 Federal (65%)

\$13,438,000

* In the Nickerson Beach area in Nassau County, dune (no berm) will be placed along approximately 5,000 If of shoreline. The existing berm will remain undisturbed to allow for bird nesting and foraging area for piping plovers and least terns. Deferred berm construction.

Non-Federal (35%)

** Berm will be stepped with 40 ft berm fronting the dune at +9 ft NAVD88, 20 ft width at 1V:30H slope, and 130 ft berm at +7ft NAVD88 with 1V:30H slope to waterline.

What is the Long Beach Project?

The Long Beach Project is a coastal storm risk management project, which has been designed to reduce damages from erosion, wave attack and inundation for homes and businesses along 6.8 miles of oceanfront, including Nassau County, the Town of Hempstead and the City of Long Beach.

While erosion is a problem, the most serious threat to the island is from high storm surges and waves. The present beach could be easily overtopped with direct damages to public and private property. The project adds elevation to private property. The project adds elevation to any existing dune and berm to manage risk against these damages.

The Long Beach Project includes beach nourishment and construction of a dune, in addition to the rehabilitation of existing groins and the construction of new groins. The project would use a dredge to pump sand from an offshore borrow area and place it on the beach. The initial construction of the Long Beach Project would be 100% federally funded.

The project would be maintained for 50 years through periodic sand placement on the beach, cost-shared between the project partners.

What comes next?

With the support of the NYSDEC and the local sponsors, the HSLRR and EA will be finalized. The next step is for the agencies to enter into a Project Partnership Agreement for construction in Summer 2014.

Construction will be accomplished under three contracts. Contract 1 includes groin work and is scheduled to begin in Fall 2014. Contract 2 includes additional groin work and is scheduled to begin in winter 2014. Contract 3 includes dune and berm construction and crossovers and will be constructed in 2016.

What is being presented at the Poster Session?

The poster session gives the public the opportunity to learn about the Long Beach Project and ask questions of the scientists and engineers who worked on the Project. Any questions the public may have can be answered during the poster session.

Registration

Please register Get added to our mailing list

LIST OF BOARDS

Overview

Meeting Purpose

<u>Planning</u>

- Problem Identification
- Historical Storm Water Levels
- Project Purpose
- Consideration of Environmental Impacts
- Bird Nesting and Foraging Area Incorporated into Project Design
- Where Will Sand Come From?

The Recommended Plan

- Project Layout with Dune and Berm Cross Sections
- Plan Components
- Typical Beachfill Response

Project Implementation

- Non-Federal Sponsor Responsibilities
- General Schedule

How do I comment?

The Draft Environmental Assessment for the Long Beach Project is open for public comment through March 31, 2014.

Comments can be submitted in writing, with the forms provided here today.

Comments can also be provided in writing to:

Mr. Robert Smith
USACE, Planning
26 Federal Plaza, Room 2151
New York, NY 10278
robert.j.smith@usace.army.mil

You can view these posters, the Hurricane Sandy Limited Reevaluation Report (HSLRR), Environmental Assessment (EA) and additional information at our website.

www.nan.usace.army.mil/LongBeach

The written comments will be assessed and considered in finalizing the Environmental Assessment

Additional Contacts:

Ronald Pinzon, USACE Project Manager ronald.r.pinzon@usace.army.mil

Sue McCormick, P.E., NYSDEC Program Manager sdmccorm@gw.dec.state.ny.us





LONG BEACH COASTAL STORM RISK MANAGEMENT PROJECT

PUBLIC INFORMATION SESSION

Atlantic Coast of Long Island
Jones Inlet to Rockaway Inlet
Draft Hurricane Sandy
Limited Reevaluation Report
and
Draft Environmental Assessment

US Army Corps of Engineers (USACE) and

New York State Department of Environmental Conservation (NYSDEC)

In cooperation with: City of Long Beach Town of Hempstead Nassau County

March 6, 2014

6:00-6:30pm Welcome & Poster Viewing 6:30-6:40pm Non-Federal Local Sponsors 6:40-7:00pm US Army Corps of Engineers 7:00-8:00pm Poster Board Session & Information Exchange