Fire Island Inlet to Montauk Point, NY Final General Reevaluation Report



APPENDIX C COST ENGINEERING

U.S. Army Corps of Engineers New York District

February 2020

FIRE ISLAND TO MONTAUK POINT REFORMULATION STUDY – FINAL GRR $\underline{\mathbf{Appendix}\ C}$

Cost Engineering

Table of Contents

Introduction	3
Table C-1 – Initial Construction Costs and MII/Cost Backup (Project First Cost)	7
Table C-2 – Annualized Cost	8
Table C-3 – Renourishment Cost	9
Table C-4 – Emergency Beach Fill Cost	10
Table C-5 – Environmental Monitoring Cost	12
Table C-6 – Engineering Monitoring Cost	13
Table C-7 – Cost Apportionment	14
Total Project Cost Summary	15
Cost & Schedule Risk Analysis (CSRA) Results	16
Schedule	17
ATR/Cost Certification	18

Introduction

The draft GRR and EIS that included the TSP were released in July 2016 for public and agency comment. Based on the comments received and further coordination with DOI and NYS subsequent to the public comment period, a recommended plan was identified that is supported by DOI and NYS. Since the recommended plan included project features that were not part of the National Economic Development (NED) Plan, a policy exception was requested and granted by the Assistant Secretary of the Army (Civil Works) on Oct 11, 2017. The policy exception allows USACE to recommend the "mutually acceptable" plan consistent with requirement of the authorizing law, Section 8 of Public Law 88-587 that established Fire Island National Seashore. The Recommended Plan is the "mutually acceptable Plan" identified to the Secretary of the Army and Secretary of the Interior, and supported by the non-Federal sponsor, includes the following:

Inlet Sand Bypassing

- Provides for sufficient sand bypassing across Fire Island, Moriches, and Shinnecock Inlets to restore the natural
 longshore transport of sand along the barrier island for 50 years. Scheduled O&M dredging of the authorized
 navigation channel and deposition basin with sand placement on the barrier island will be supplemented, as
 needed, by dredging from the adjacent ebb shoals of each inlet to obtain the required volume of sand needed for
 bypassing.
- The bypassed sand will be placed in a berm template at elevation +9.5 ft NGVD 29 in identified placement areas.
- Monitoring is included to facilitate adaptive management changes.

Mainland Nonstructural Measures

- Includes up to 4,432 structures within the ten percent floodplain using nonstructural measures, primarily, structural elevations and floodproofing, based upon structure type and condition.
- Ringwalls are provided for 93 structures that are not suitable for nonstructural measures. The ringwalls will meet all requirements of structural measures.
- Includes acquisition of 14 structures in areas subject to high frequency flooding, and reestablishment of natural floodplain function.

Breach Response on Barrier Islands

- <u>Proactive Breach Response</u> is an action that is triggered when the level of project performance at the shoreline falls below the condition under which the four percent flood would be capable of breaching the barrier island.
- Reactive Breach Response is an action that is triggered when a breach has occurred, and there is an exchange of ocean and bay water during normal tidal conditions. It is applicable to locations where there is agreement that a breach should be mechanically closed quickly, such as the Talisman Federal tract, where there is an acknowledgement of the high vulnerability of breaching, deep water in the back bay, and new infrastructure that connects communities east and west of this location.
- <u>Conditional Breach Response</u> is an action that is triggered when a breach has occurred, and there is an exchange of ocean and bay water during normal tidal conditions. It is applicable to most Federally-owned tracts within FIIS. A decision about potential breach closure will be made by the Breach Closure Team. Mechanical closure of the breach will take place if the breach does not close naturally within 60 days of opening.
- Wilderness Breach Response is an action that is triggered when a breach has occurred, and there is an exchange of ocean and bay water during normal tidal conditions. It is applicable to the Federally-owned Wilderness tracts within FIIS, and is consistent with the Wilderness Breach Management Plan/EIS prepared by NPS. A decision about potential breach closure will be made by the Breach Closure Team. Mechanical closure of the breach may take place if decided by the Breach Closure Team.

Beach and Dune Fill on Shorefront

- Provides for a 90 ft width berm and +15 ft dune along the developed shorefront areas on Fire Island and Westhampton barrier islands.
- All dunes will be planted with dune grass except where noted.

- On Fire Island the post-Hurricane Sandy optimized alignment is followed and includes overfill in the developed locations to minimize tapers into Federal tracts.
- Renourishment takes place approximately every 4 years for up to 30 years after project completion; while proactive breach response takes place from years 31 to 50. Inlet bypassing and CPF renourishment takes place for 50 years on the same cycle timeline.
- Provides for adaptive management to ensure the volume and placement configuration accomplishes the design objectives of offsetting long-term erosion.
- Provides for construction of a feeder beach every 4 years for up to 30 years at Montauk Beach.

Groin Modifications

Contract 1

Provides for removal of the existing Ocean Beach groins.

Coastal Process Features (CPFs)

- Provides for 12 barrier island locations and two (2) mainland locations as coastal process features and provide habitat for protected species.
- Includes placement of approximately 4.2 M cy of sediment to be placed along the barrier island bayside shoreline over the 50-year period of analysis that reestablishes the natural coastal processes consistent with the reformulation objective of no net loss of habitat or sediment. The placement of sediment along the bay shoreline will be conducted in conjunction with other nearby beach fill operations undertaken on the barrier island shorefront.

- Dredging at Fire Island Inlet with sand placement on Gilgo Beach and Robert Moses State Park

The planned contract structure for this project is as follows:

Contract 2	- Dredging at Moriches and Shinnecock Inlets with sand placement within sub-reaches MB 1A,
	1B, 2A and SB 1D and 2B, and also at the New Made Island and Pattersquash CPF's.
Contract 3	- Dredging at offshore borrow sites with sand placement within sub-reaches SB- 1B, 1C, 1D
	and M-1 F (Montauk feeder beach).
Contract 4	- Dredging at offshore borrow site with sand placement within sub-reaches MB- 2C, 2D, 2E
	(Westhampton vicinity)
Contract 5	- Groin modification at Ocean Beach
Contract 6	- Year 1 Non-Structural measures (500 structures)
Contract 7	- Year 2 Non-Structural measures (1,000 structures)
Contract 8	- Year 3 Non-Structural measures (1,250 structures)
Contract 9	- Year 4 Non-Structural measures (1250 structures)
Contract 10	- Year 5 Non-Structural measures (432 structures)

Separate – No contracts planned/required: Breach closure, renourishment, and Monitoring.

Dredging/beachfill costs have been estimated in CEDEP and the unit costs for mob/demob and dredging have been transferred to MII in a typical fashion for dredging work. The groin work has been included in the MII estimate with typical labor/eq/material setup. Both dredging and groin work have been assumed to go out under Unrestricted/Full & Open acquisition methods. The work in the estimates have been assigned mostly to the Prime Contractor, who is assumed to be capable of performing most of the work.

The non-structural estimates for contracts 6-10, though founded in MII, are based on Microsoft Excel since that is the export program used by the algorithm to determine the N-S pricing by the A/E. The basis for those input costs were generated in MII using labor/eq/materials for single structures and the associated fixes. The acquisition strategy for the non-structural cost is akin to a MATOC or Small Business, where the performing

contractors are mostly subcontractors of the Prime. Those individual MII costs for each individual non-structural fix were input into the simulation, which spit out the corresponding fixes for each of the structures in the inventory.

The Breach Response costs were developed by a computer program from an A/E, based on likelihood of occurrence in any given year due to the storm models. The risk simulations identify the occurrence of breaches by future year with about 10,000 random storm lifecycles. The simulated number of response actions over the lifecycles are extracted, and have closure cost values in the model. The annualized costs are the results from the model; as only in the annualized costs (used as the basis for B/C ratio).

Physical and Environmental Monitoring costs were developed by NY District Engineering & Environmental PDT members, resectively. The adaptive management/breach closure costs were developed by AECOM. The output from their monte carlo simulation provided an annualized cost number for the breach closure plan; this number was assumed for every year in the 50 year project life. For TPCS purposes, it was broken down into 4 year increments (to align with the renourishment schedule) and escalated to the midpoint of those 4 years in order to show a concise listing.

There is also continuing construction costs, for periodic renourishment for the beachfill. The cycle is every 4 years, for 50 years, for a total of 13 renourishment cycles. The areas to receive renourishment are mainly in contracts. Similarly, both the engineering and the environmental monitoring costs are estimated for 50 years. Note that only the inlet bypassing and CPF nourishment is for 50 years; otherwise renourishment is for 30 years, with proactive breach response for years 31-50. Table 31 of the Main Report provides a description by sub-reach of what is provided over the project life cycle.

With regards to net benefits and beachfill plan 3a providing the greatest storm damage reduction benefits (as outlined in the Main Report), there was not a Cost ATR conducted on the project cost estimates used to determine the benefits - the initial formulation estimates were done several years ago (sometime around 2009-2010). The initial formulation efforts, which included an initial Screening of Measures, preliminary design of alternatives, and design optimization are described in detail in Appendix E - Plan Formulation. In May 2009, a draft Formulation Report was provided to the partner agencies, the Department of Interior and the State of New York Department of Environmental Conservation for review and comment. There is no record of an ATR performed on these measures/alternatives.

Lands and Damages (01 Account) costs were received from Real Estate Division. Contract 2 is the only one with no real estate costs assigned to it.

The periodic renourishment volumes at each location are to be placed at 4-year cycles subsequent to commencement of construction and throughout the 30-year economic life. For contracts 1 and 2, the renourishment volumes are to be placed every 2 years. As such, the cost for these two reaches have been doubled in the calculation of renourishment costs for the 4-year cycles. The renourishment beach fill is assumed to be placed in the same manner as the beach fill for the main contracts; with a large hopper dredge pumping the fill onto the shore, and a shore crew placing the material. Additional renourishment costs due to adapting the design for the "intermediate" sea-level change (SLC) scenario have been incorporated into the costs as well. They can be found on the last page of the TPCS, and backup can be found in the cost product documentation and after the annualized renourishment costs shown in Table C-2.

Major rehabilitation costs are for restoring the design profile due to significant storm events beyond those that were designed for in the renourishment cycle. The threshold at which major rehabilitation costs are incurred is based on the storm event that causes the erosion volume to exceed 15 cy/lf along the beach front. This is the

average nourishment volume anticipated to be available at the midpoint of the renourishment cycle because the significant storm event has a 50% chance of occurring earlier or later than the cycle midpoint. Annualized major rehab costs are shown in Table C-3.

Monitoring Costs are shown in Table C-4; additional information on these costs can be found in the Monitoring Appendix (Appendix I).

The Cost Apportionment for this project can be found in table C-5. The initial construction cost is 100% Federally-Funded; however, the continuing construction costs are shared by the Federal Government and the local sponsor. The cost share for coastal restoration projects is 65%/35%. O&M and Major Rehab costs are the responsibility of the non-Federal sponsor.

The TSP with the Intermediate SLC scenario has been certified. The TSP was previously certified by Walla Walla in August of 2016. Both the current and previous certifications can be found at the end of this appendix.

Note - the costs presented in this appendix represent the intermediate SLC scenario. The reduction in cost from what is shown for the Low SLC scenario is simply the removal of the SLC Adaptation costs from the 'Continuing Construction' costs, which amount to \$26.16m. The array of costs for the different scenarios can be found in Table C-2, where the costs and benefits for the Low, Intermediate, and High SLC Scenarios are all shown. Additionally, the SLC adaptation cost is shown in Table C-7. The Low SLC version of this table is shown in pdf below, for comparison (double click to open).

	Federal Share	No	n-Federal Share		Total		
					Total		
\$	1,367,656,000	\$	_	\$	1,367,656,000		
	153,277,000	\$	-	\$	153,277,000		
\$	1,520,933,000	\$	-	\$	1,520,933,000		
\$	85,936,000	\$	85,936,000	\$	171,872,000		
\$					942,185,000		
					110,331,000		
\$	35,030,000	\$	18,862,000	\$	53,892,000		
	76 270 000		41.060.000		117,339,000		
_		_		_			
5	881,371,000	\$	514,248,000	3	1,395,619,000		
\$	2,402,304,000	\$	514,248,000	\$	2,916,552,000		
\$	-	\$	56,329,000	\$	56,329,000		
\$	-	\$	660,000	\$	660,000		
\$	-	\$	56,989,000	\$	56,989,000		
tructio	n and renourishn	nent					
re 509	6 Federal, 50% N	Von-I	ederal.				
re 659	6 Federal, 35% N	Von-I	ederal.				
in the	Environmental ?	Moni	toring Cost Tabl	le			
milari	to renourishment						
	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	\$ 612,420,000 \$ 71,715,000 \$ 35,030,000 \$ 76,270,000 \$ 881,371,000 \$ 2,402,304,000 \$	\$ 612,420,000 \$ 71,715,000 \$ \$ 71,715,000 \$ \$ 35,030,000 \$ \$ \$ 35,030,000 \$ \$ \$ 881,371,000 \$ \$ \$ 881,371,000 \$ \$ \$ 2,402,304,000 \$ \$ \$ - \$ \$ \$ - \$ \$ \$ - \$ \$ \$ \$ - \$ \$ \$ \$ - \$ \$ \$ \$ \$ - \$ \$ \$ \$ \$ - \$	\$ 612,420,000 \$ 329,765,000 \$ 71,715,000 \$ 35,616,000 \$ 35,616,000 \$ 35,030,000 \$ 18,862,000 \$ 18,862,000 \$ 18,862,000 \$ 5.14,248,000 \$ 514,248,000 \$ 514,248,000 \$ 5.402,304,000 \$ 514,248,000 \$ - \$ 56,329,000 \$ - \$ 56,329,000 \$ - \$ 56,989,000 \$ - \$ 56,989,000 \$ - \$ 56,989,000 \$ 10,000 \$ - \$ 56,989,000 \$ 10,0	\$ 612,420,000 \$ 329,765,000 \$ \$ 71,715,000 \$ \$ 38,616,000 \$ \$ 38,616,000 \$ \$ 35,030,000 \$ 18,862,000 \$ \$ \$ 76,270,000 \$ 41,069,000 \$ \$ 881,371,000 \$ 514,248,000 \$ \$ 2,402,304,000 \$ 514,248,000 \$ \$ \$ - \$ 56,329,000 \$ \$ \$ - \$ 56,329,000 \$ \$ \$ - \$ 56,60,000 \$ \$ \$ - \$ 56,60,000 \$ \$ \$ - \$ 56,989,000 \$ \$ \$ \$ - \$ 56,989,000 \$ \$ \$ \$ - \$ 56,989,000 \$ \$ \$ \$ - \$ 56,989,000 \$ \$ \$ \$ \$ - \$ 56,989,000 \$ \$ \$ \$ \$ - \$ 56,989,000 \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$		

Table C-1 - Initial Construction Costs and MII/Cost Backup (Project First Cost)

(double-click to open in Adobe)

FIRE ISLAND INLET TO MONTAUK POINT, NY Tentative Selected Plan with Post Sandy Amendments Summary of Components

L	Contracts	NOTES	Cost	Duration (Mo.)	Contract Start (NTP)	Midpoint	Finish	PRICE LEVEL
2 3 4 5 6 7 8 9 10	Inlet Dredging: Fire Island Inlet Dredging: Moriches, Shiranoock Tisan Bonsh, Downtown Montask Beachfill Smith's Points/Westhampton Bonehfill Onean Bonch Groin Modifications Year 1 Non-Structural Inventory Year 2 Non-Structural Inventory Year 3 Non-Structural Inventory Year 3 Non-Structural Inventory Year 4 Non-Structural Inventory Year 5 Non-Structural Inventory Year 5 Non-Structural Inventory Fact 5 Non-Structural Inventory Fact 5 Non-Structural Inventory Contact Process Features - Initial Only Fish & Wildlife Facilities Costs (Initial Enviro Monitoring) Cultural Resources	First Cost	\$ 22,422,681 \$ 14,576,308 \$ 30,759,113 \$ 11,618,877 \$ 73,610,178 \$ 147,220,356 \$ 184,025,445 \$ 184,025,445 \$ 64,188,075 \$ 186,023,391 \$ 780,000 \$ 11,500,000	8.00 7.00 7.00 7.00 6.00 14.00 14.00 14.00 14.00 14.00 14.00 14.00 14.00	10-Nov-20 16-Apr-21 10-Nov-20 14-Jun-21 3-Sep-21 5-Sep-22 7-Sep-23 5-Sep-24 8-Sep-25 7-Sep-26 11-Feb-21	27-Feb-21 29-Jul-21 10-Feb-21 16-Sep-21 30-Mer-23 31-Mer-24 30-Mer-25 2-Apr-26 1-Apr-27 22-May-21	17-Jun-21 11-Nov-21 13-May-21 20-Dec-21 18-Feb-22 23-Oct-23 24-Oct-24 23-Oct-25 26-Oct-25 25-Oct-27 30-Aug-21	Oct-18

Total: \$ 766,613,365 (tracks to CWBS Initial contract cost on TPCS :ummary sheet, cell M24)

Project Duration: 109 months

Does not include cost-shared costs - renourishment, monitoring, breach closure

Table C-2 - Annualized Cost

(double-click to open in Adobe)

Table C-2: Annualized Cost Summary - Recommended Plan Price level October 2018, Federal Discount Rate 2.875%, Base year 2028										
	Price level October 2018, Federal Discount K	Low SLC*	Intermediate SLC*	High SLC*						
	02 Relocations	90	\$0	02						
	06 Fish & Wildlife Facilities	\$1,016,000	\$1,016,000	\$1,016,000						
	10 Breakwater & Seawalls	\$5,033,900	\$5,033,900	\$5,033,900						
	17 Beach Replenishment	\$126,872,400	\$126,872,400	\$126,872,400						
	18 Cultural Resources	\$14,979,900	\$14,979,900	\$14,979,900						
	19 Buildings, Grounds & Utilities	\$850,688,300	\$850,688,300	\$850,688,300						
	Construction Estimate Totals	\$998,590,500	\$998,590,500	\$998,590,500						
	01 Land and Damages	\$153,276,600	\$153,276,600	\$153,276,600						
	30 Planning, Engineering & Design	\$281,281,000	\$281,281,000	\$281,281,000						
	31 Construction Management	\$87,784,800	\$87,784,800	\$87,784,800						
	Project Cost Totals	\$1,520,932,900	\$1,520,932,900	\$1,520,932,900						
	IDC	\$29,661,300	\$29,661,300	\$29,661,300						
	Investment Cost	\$1,550,594,200	\$1,550,594,200	\$1,550,594,200						
	International Cost	ATTO ATTO	A POST POST POST POST POST POST POST POST	42,000,004,000						
	Amortized Investment Cost	\$58,842,000	\$58,842,000	\$58,842,000						
	Periodic Renourishment for 30 years	\$20,879,000	\$20,879,000	\$20,879,000						
	Inlet Bypassing for 50 years (includies obb shoal dreding)	\$9,340,000	\$9,340,000	\$9,340,000						
菱	Proactive Breach Closure	\$685,000		\$468,000						
An mu alized Cos			\$636,000							
2	Breach Closure Costs	\$839,000	\$1,162,000	\$3,060,000						
-	Coastal/Engineering Monitoring Environmental Monitoring	\$1,264,300 \$2,332,000	\$1,264,300 \$2,332,000	\$1,264,300						
E		\$659,600	\$659,600	\$2,332,000						
- 5	O&M			\$659,600						
	Emergency Beach Fill	\$1,891,000	\$1,891,000	\$1,891,000						
	SLC Adaptation (1)	02	\$647,000	\$3,134,000						
	Total Annual Cost	\$96,731,900	\$97,652,900	\$101,869,900						
8	Damages - Breach Open	\$9,314,000	\$26,999,000	\$139,081,000						
Amages	Damages - Back Bay Inundation	\$77,920,000	\$81,351,000	\$256,539,000						
3	Damages - Shore Front	\$7,002,500	\$8,004,000	\$13,450,000						
•	Total Damages	\$94,236,500	\$116,354,000	\$409,070,000						
	Benefits - Breach Open	\$10,148,000	\$33,268,000	\$482,197,000						
	Benefits - Back Bay Inundation	\$81,572,000	\$133,317,000	\$288,701,000						
	Benefits - Shore Front	\$8,293,000	\$8,289,000	\$7,926,000						
	Total Storm Damage Reduction Benefits	\$100,013,000	\$174,874,000	\$778,824,000						
	Cost Avoided - Breach Closure	\$3,148,000	\$4,296,000	\$11,558,000						
	Non-Federal Renourishment Cost Avoided	3.007,200	3.007.200	3,007,200						
	Recreation Benefits	\$24,623,000	\$24,623,000	\$24,623,000						
	Total Benefits	\$130,791,200	\$206,800,200	\$818,012,200						
	Net Benefits (Damage Reduction Only)	\$34,059,300	\$109,147,300	\$716,142,300						
	BCR	1.35	2.12	8.03						
. T8T-0		Lab	2.12	8.03						

1 - Low SLC, Int. SLC, and High SLC based on USACE guidance. ETL, dated 30 June 2014.

Table C-3 - Renourishment Cost

(double-click to open in Adobe)

Fire Island to Montauk Point, NY

FIMP Periodic Nourishment Costs Recommended Plan (Oct 18 PL)

Talat Managaran Contr. (Day 4 on Brownighteness)				20 652 564
Inlet Management Costs (Per 4-yr Renourishment C	.ycie)	Mob & Demob	\$	28,652,564
		Subtotal		28,653,000
	Contingency	30.26%	•	8,671,000
	Contingency	E&D		2,985,900
	Constructi	ion Management		2,851,500
		st Per Operation	_	43,161,400
	Total Co	stre operation	•	45,101,400
Renourishment/Sediment Management			5	79,216,000
Costs (Per 4-vr Renourishment Cycle: Yr 4 Only)		Mob & Demob	Š	13,352,000
		Subtotal	5	92,568,000
	Contingency	30.26%	Š	28,012,000
		E&D	\$	9,646,300
	Constructi	ion Management	\$	7,922,600
	Total Co	st Per Operation	\$	138,148,900
		-		
Renourishment/Sediment Management				\$59,315,000
Costs (Per 4-yr Renourishment Cycle; Yrs 8-23 On	ly)	Mob & Demob	\$	13,352,000
	_	Subtotal	\$	72,667,000
	Contingency	30.26%	\$	21,990,000
		E&D	\$	7,572,500
	Constructi	ion Management	\$	6,428,300
	Total Co	st Per Operation	\$	108,657,800
Renourishment/Sediment Management				\$81,964,000
Costs (Per 6-vr Renourishment Cycle: Yrs 24-30 O	nly)	Mob & Demob	\$	13,352,000
		Subtotal	\$	95,316,000
	Contingency	30.26%	\$	28,843,000
		E&D	\$	7,572,500
		ion Management	_	6,194,100
	Total Co	st Per Operation	\$	137,925,600
Ebb Shoal				\$17 270 400
	-l-A	Mob & Demob		\$17,370,400
Costs (Per 4-yr Renourishment Cycle; Yrs 31-50 O	шүј	Subtotal	•	17,371,000
	Contingency	30.26%		5,257,000
	Contingency	E&D		1,810,200
	Constructi	ion Management		1,832,000
		st Per Operation	_	26,270,200
	Total Co	A ra operation	•	20,270,200

Table C-4 – Emergency Beach Fill Cost (double-click to open in Adobe)

Fire Island to Montauk Point, NY

FIMP Emergency Beach Fill Costs (Oct 18 PL)

Return Period	Frequency	Frequency Interval	Permanent Loss Factor	Erosion Volume	Emergency Fill	Average Emergency Fill	Average Emergency Fill	Annual rgency Fill	Annual Emergency Fil
(yr)	(events/yr)		(%)	(cy/ft)	(cy/ft)	(cy)	(\$)	(\$)	(cy/yr)
10	0.1		16%	18.50	2.96				
		0.05				233,050	\$8,156,744	\$ 407,837	11,652
20	0.05		22%	20.69	4.55				
		0.03				327,262	\$11,454,168	\$ 343,625	6,545
50	0.02		27%	22.21	6.00				
		0.01				421,316	\$14,746,053	\$ 147,461	4,213
100	0.01		33%	22.98	7.58				
		0.005				515,149	\$18,030,229	\$ 90,151	2,576
200	0.005		38%	23.74	9.02				
otal Fill Length (ff):	62,049	63,095						
otal Fill Length (ff OTAL REHABII	•		63,095			1,496,777			24,9

MB-2C-2E (Westhampton)											
Return Period	Frequency	Frequency Interval	Permanent Loss Factor	Erosion Volume	Emergency Fill	Average Emergency Fill	Average Emergency Fill		Annual ergency Fill	Annual Emergency Fil	
(yr)	(events/yr)		(%)	(cy/ft)	(cy/ft)	(cy)	(\$)		(\$)	(cy/yr)	
10	0.1		16%	15.25	2.44						
		0.05				76,941	\$2,692,924	\$	134,646	3,847	
20	0.05		22%	17.07	3.76						
		0.03				108,872	\$3,810,534	\$	114,316	2,177	
50	0.02		27%	18.56	5.01						
		0.01				141,331	\$4,946,575	\$	49,466	1,413	
100	0.01		33%	19.30	6.37						
		0.005				173,906	\$6,086,701	\$	30,434	870	
200	0.005		38%	20.09	7.63						
otal Fill Length (ff):	24.838	26,872								
OTAL REHABII			,			501,050				8,307	

Subtotal Annualized Emergency Fill Cost \$1,318,000 \$15.17

Subtotal Emergency Fill (every 4 year total): \$5,272,000

Construction Contingency: \$1,595,000 E&D (Incl. Contingency): \$549,000

S&A (Incl. Contingency): \$631,000

Total Emergency Fill Cost (every 4 year total): \$8,047,000

Total Emergency Fill for Project: \$56,329,000
Total Annualized Emergency Fill Cost: \$1,891,000

Notes:

Loss Factor: This is the percent of eroded volume permanently lost to the profile. The factors are based on experience at Ocean City, Md.

Erosion Volume:

Maximum erosion volume landward of a given profile position computed from SBEACH (50,100 and 200 year storms extraploated from northeasters)

Emergency Fill Cost: Based on for trucked sand (cy) = \$33

Full Cost (With E&D/S&A and Contingency)

		PRESENT	
	FUTURE	WORTH	PRESENT
YEAR	WORK	FACTOR	WORTH
0	\$0	1.00000	\$0
4	\$8,047,000	0.89281	\$7,184,468
8	\$8,047,000	0.79712	\$6,414,388
12	\$8,047,000	0.71168	\$5,726,850
16	\$8,047,000	0.63539	\$5,113,008
20	\$8,047,000	0.56729	\$4,564,961
24	\$8,047,000	0.50648	\$4,075,657
28	\$8,047,000	0.45219	\$3,638,801
32	\$8,047,000	0.40372	\$3,248,769
36	\$8,047,000	0.36045	\$2,900,544
40	\$8,047,000	0.32181	\$2,589,644
44	\$8,047,000	0.28732	\$2,312,068
48	\$8,047,000	0.25652	\$2,064,245
SUM OF PRESENT WORTHS	\$96,564,000		\$49,833,403
TOTAL ANNUAL COST			\$1,891,000

Interest Rate 2.875%

n=50 years

Appendix o out Engineering

FIMP Reformulation Study - Final GRR

50

Table C-5 – Environmental Monitoring Cost (double-click to open in Adobe)

Fire Island to Montauk Point (FIMP)

Environmental Monitoring Costs

		PRESENT	
1	\$8,505,980	0.97205	\$8,268,267
2	\$2,123,240	0.94489	\$2,006,224
3	\$2,123,240	0.91848	\$1,950,157
4	\$2,123,240	0.89281	\$1,895,657
5	\$2,123,240	0.86786	\$1,842,680
6	\$2,123,240	0.84361	\$1,791,183
7	\$2,123,240	0.82003	\$1,741,126
8	\$2,123,240	0.79712	\$1,692,467
9	\$2,123,240	0.77484	\$1,645,169
10	\$2,123,240	0.75318	\$1,599,192
11	\$2,123,240	0.73214	\$1,554,500
12	\$2,123,240	0.71168	\$1,511,057
13	\$2,123,240	0.69179	\$1,468,828
14	\$2,123,240	0.67245	\$1,427,780
15	\$2,123,240	0.65366	\$1,387,878
16	\$2,123,240	0.63539	\$1,349,092
17	\$2,123,240	0.61764	\$1,311,389
18	\$2,123,240	0.60038	\$1,274,741
19 20	\$2,123,240 \$2,123,240	0.58360	\$1,239,116 \$1,204,487
21	\$2,123,240	0.55143	\$1,170,826
22	\$2,123,240	0.53602	\$1,138,105
23	\$2,123,240	0.52104	\$1,106,299
24	\$2,123,240	0.50648	\$1,075,382
25 26	\$2,123,240	0.49233 0.47857	\$1,045,329
27	\$2,123,240 \$2,123,240	0.46519	\$1,016,115 \$987,718
28	\$2,123,240	0.45219	\$960,115
29	\$2,123,240	0.43956	\$933,283
30	\$2,123,240	0.42727	\$907,201
31 32	\$2,123,240 \$1,992,980	0.41533 0.40372	\$881,848 \$804,614
33	\$1,992,980	0.39344	\$782,128
34	\$1,992,980	0.38147	\$760,270
35	\$1,992,980	0.37081	\$739,024
36	\$1,992,980	0.36045	\$718,370
37 38	\$1,992,980 \$2,123,240	0.35038	\$698,294 \$723,144
38 39	\$1,992,980	0.34059	\$659,810
40	\$1,992,980	0.32181	\$641,371
41	\$1,992,980	0.31282	\$623,446
42	\$1,992,980	0.30408	\$606,023
43 44	\$1,992,980 \$1,992,980	0.29558	\$589,087 \$572,624
45	\$1,992,980	0.27929	\$556,621
46	\$2,123,240	0.27149	\$576,429
47	\$1,992,980	0.26390	\$525,945
48	\$1,992,980	0.25652	\$511,246
49 50	\$1,992,980	0.24935 0.24239	\$496,959 \$483,071
30	\$1,557,560	0.24239	a-183,071
Contingency %: Sum of Present Worths:	30.26% \$110,331,000		\$61,451,690
TOTAL ANNUAL COST			\$2,332,000

Table C-6 – Engineering Monitoring Cost (double-click to open in Adobe)

(Cristo Will Prin Lond)																		
PROJECT	MOST	MATE VANTE BYANCTURE BEFECTION	LONG NAMES BEACH PROPLES	LONG MANGE CMF PROPLES	SECURENT SAMPLES	LIGAR TOPOGRAPHY	BATRY BETRY	HLET ADD	MODELING	WANT.	UNITED GASES	BASICH BAY PROFUSE	TOPOGRAPHY	AREA MONETOR	MES	ARCHEST TEMBORT BOOKING	SATA ANALYSIS (MENCAT)	TOTAL
Preson.		4,800	773,000	224,880	175,300	394,000	256,000	170,000	180,000	754,000	401,000	90,000			21,000	1,147,000		4,877,100
		18,300	793,000	224,000	12,300	793,000				375,000	1915,000				21,000	401,000	72,000	2,611,790
3		14,400	710,800	224,880	37,300	793,000				378,000	162,000				21,000	781,000	34,000	3,231,000
3		14,400	710,800	224,880	12,300	793,000				378,000	162,000				21,000	380,000	34,000	2,801,000
4		14,400	710,800	224,880	120,230	793,000				304,000	193,000				21,000	133,000	34,000	2,489,400
3		8,400			12,300						191,000				21,000			239,100
	2	8,400			37,300						191,000				21,000			364,100
7	-	8,400			12,300						191,000				21,000			239,100
		8,400	374,000	112,880	120,230	394,000					191,000				21,000		73,000	1,307,830
		1,400			13,300						191,000				21,000			230,100
10		8,400			37,300		204,000	200,000	380,000		191,000	99,000	394,000		21,000		73,000	1,847,100
113	3	8,400			13,300						193,000				21,000			236,100
12		8,400	274.000	112,000	120,230	394.000					193,000				23,000		77.000	1.307.830
- 12		1,600			12,300						197,000				21,000			236,100
14		1,600			37,300						162,000		_		21,000			364,100
10	•	5,600			12,300						193,000		_		21,000			296,100
14		8,400	374,000	112,800	120,230	394,000					162,000				21,000		72,000	1,307,850
13		1,600			12,500						162,500				21,000			29(10)
- 18	5	8,400			37,300			_			193,000		_		21,000			264.100
38		1,400	374,000	113,860	123,230	394,000	354,000	200,000	380,000		195,000	98,000	394,000		21,000		144,000	296,100 2,890,850
21		1,600		110,000	12,300	and the same of	1000000	-	-		193,000				21,000			276,100
23	6	8,400			37,300						193,000				21,000			264.100
		1,600			12,300						191,000				21,000			294,100
34		1,600	374,000	112,800	120,230						105.000 105.000		_	18,100	21,000		72.000	1.307.830
26	_	8,400			17,300						193,000			346,000	21,000			264.100
27	7	1,600			12,300						195.000				21,000			270.100
		9,600	374,500	115,860	125,236						100,000				21,000		72,000	1,381,000
28		1,600			12.300						162,000				21,000			239.100
27	8	9.600	-		17,300		196,000	200,000	180,000		180,000	95.000	394,000		20,000	_	72,000	1.847.100 239.100
22		9,000	144,000	112,000		300.000					180,000				28,000		73,000	1,073,000
30 34		9.000			12,500						100,000				25,000			200,100
34	9	9,800			27,500						183,000				28,000			384,100
-		9.000			12,500	-					193,000				28,000			239,100
37		9.800	144000	112.000	125.200	386.000					180,000				25,000		72,000	1,075,850
-		9.000			27 500						100,000		_		2000			204.100
	10	8,800			12,500						180,000				20,000			200,100
		9.00	144,000	112,000			506,000	200,000	300,000		100,000	99,000	300,000		25,000		164,000	2,758,850
-		9.800			12.500 37.500						120,000				25.000			200 100 200 100
0	11	9,000			37,500 12,500						180,000				2,000			200,100
44		9.00	144,000	112.000	128,200	36.00					120,000				2.00		73.000	1,075,800
4 0		9,000			12,500						180,000				28,000			239,100
	12	9.000			27.500						120,000				2.00			26133
e e		9.02	144,000	112,000	125.200	306.000				_	12.00				200		73,000	239,100 1,073,800
	4.5	9.00	144,233	112,000	12,500	300,000					180,000				2,00		72,000	239,100
- 10	13	1,80			27.500			50,000			100,000	30,00	300,000		2,00		186,000	877,100
200		108,800	4.794.000	1370.000	1478.100	7,000,000	148100	1,000,000	1,980,000	3,014,000	10.003.000				1271.000	2,836,000	1,0300	46,279,100

Table C-7 - Cost Apportionment

(double-click to open in Adobe)

FIMP, Fire Island Inlet to Montauk Point, NY

Cost Apportionment*									
Cost-Sharing		Federal Share		Total					
Project First Costs									
Cash Contribution	\$	1,367,656,000	\$	-	\$	1,367,656,000			
Real Estate Lands & Damages	\$	153,277,000	\$	-	\$	153,277,000			
TOTAL FIRST COST	\$	1,520,933,000	\$	-	\$	1,520,933,000			
Continuing Construction First Cost									
Scheduled Beach Renourishment, Westhampton & Pikes (a)	\$	85,936,000	\$	85,936,000	\$	171,872,000			
Scheduled Beach Renourishment, All Others (b)	\$	612,420,000	\$	329,765,000	\$	942,185,000			
Environmental Monitoring (e)	\$	71,715,000	\$	38,616,000	\$	110,331,000			
Engineering Monitoring	\$	35,030,000	\$	18,862,000	\$	53,892,000			
SLC Adaptation	\$	17,009,000	\$	9,159,000	\$	26,168,000			
Breach Closure (d)	\$	76,270,000	\$	41,069,000	\$	117,339,000			
SUBTOTAL CONTINUING CONSTRUCTION COST	\$	898,380,000	\$	523,407,000	\$	1,421,787,000			
TOTAL CUMULATIVE CONSTRUCTION COST (e)	\$	2,419,313,000	\$	523,407,000	\$	2,942,720,000			
Emergency Beach Fill (f)	\$	_	\$	56,329,000	\$	56,329,000			
Annual Beach & Groin Maintenance Cost	\$	-	\$	660,000	\$	660,000			
TOTAL ANNUAL O&M COSTS	\$	-	\$	56,989,000	\$	56,989,000			

^{*} October 2018 Price Level

^{**} Shared based on 65% Federal and 35% non-Federal for construction and renourishment

⁽a) Beach Renourishment = roughly every 4-year cycle; cost share 50% Federal, 50% Non-Federal.

⁽b) Beach Renourishment = roughly every 4-year cycle; cost share 65% Federal, 35% Non-Federal.

⁽c) Environmental Monitoring varies yearly and is broken down in the Environmental Monitoring Cost Table

⁽d) Both Proactive and Reactive breach closure costs

⁽e) Cumulative Costs include Total First Cost and Cumulative Construction

⁽f) Emergency Beach Fill = Assumed to happen every 4 years similar to renourishment


Total Project Cost Summary (double-click to open in Adobe)


OJECT:		**** TOTAL PROJECT COST SUMMARY **** Icland to Montauk Point, General Reevaluation Report DISTRICT: New York District												PARED:	Page 1 of 28 9/20/2019		
	Fire Island to Montauk Point, NY	FIMP GRR							POC:	CHIEF, CO	BT ENGINEES	RING, Muk	sch Kuma	,			
Civil Works Work Breakdown Structure			ESTIMATED COST				PROJECT FIRST COST (Constant Dollar Basis)						TOTAL PROJECT COST (FULLY FUNDED)				
								Program Yes Effective Pr	r (Budget EC): foe Level Date:	2019 1 OCT 18							
WBS	CMI Works	COST	CNTG	CNTG	TOTAL	ESC	COST	CNTG	TOTAL	Spent Thru: 10/1/2018	TOTAL FIRST COST	INFLATED	COST	CNTG	RULL		
NUMBER A	Feature & Sub-Feature Description B	(SK)	D D	(%) E	(SK)	(%) G	(SIK)	(\$8)	GNO	(SK)	K		(\$80) M	(SK)	(SH)		
06	FISH & WILDLIFE FACILITIES	\$780	\$236	30.26%	\$1,016	0.0%	\$780	\$236	\$1,016	\$0	\$1,016	3.5%	\$808	\$244	\$1,08		
10	BREAKWATER & SEAWALLS	\$3,864	\$1,169	30.26%	\$5,034	0.0%	\$3,864	\$1,169	\$5,034	\$0	\$5,034	6.1%	\$4,101	\$1,241	\$5,34		
17 17	BEACH REPLENISHMENT (Initial Beachfill Only) BEACH REPLENISHMENT (Initial CPF Only)	\$79,377 \$18,022	\$24,019 \$5,454	30.26%	\$103,396 \$23,476	0.0%	\$79,377 \$18,022	\$24,019 \$5,454	\$103,396 \$23,476	\$0 \$0	\$103,396 \$23,476	17.2%	\$82,995 \$21,116	\$25,114	\$108,11 \$27,50		
18	CULTURAL RESOURCE PRESERVATION	\$11,500	\$3,480	30.26%	\$14,980	0.0%	\$11,500	\$3,480	\$14,980	50	\$14,980	53%	\$12,106	\$3,663	\$15,76		
19	BUILDINGS, GROUNDS & UTILITIES	\$853,069	\$197,619	30.26%	\$850,688	0.0%	\$853,089	\$197,619	\$850,688	\$0	\$850,688	12.7%		\$222,733	\$958,79		
	CONSTRUCTION ESTIMATE TOTALS:	\$766,613	\$231,977		\$998,591	0.0%	\$766,613	\$231,977	\$998,591	\$0	\$998,591	11.8%	\$857,189	\$259,385	\$1,116,57		
01	LANDS AND DAMAGES	\$127,730	\$25,546	20.00%	\$163,277	0.0%	\$127,730	\$25,548	\$153,277	\$0	\$153,277	5.7%	\$134,972	\$26,994	\$161,96		
30 31	PLANNING, ENGINEERING & DESIGN CONSTRUCTION MANAGEMENT	\$215,938 \$87,392	\$65,343 \$20,303	30.26%	\$281,281 \$87,785	0.0%	\$215,938 \$87,392	\$85,343 \$20,393	\$281,281 \$87,785	\$0 \$0	\$281,281 \$87,785	19.9% 24.6%	\$258,824	\$78,320 \$25,419	\$337,14 \$109,40		
	PROJECT COST TOTALS:	\$1,177,674	\$343,250	29.15%	\$1,520,933		\$1,177,674	\$343,250	\$1,520,933	\$0	\$1,520,933	13.4%	\$1,334,989	\$390,119	\$1,725,11		
	Renourishment/Monitoring/Breach Closure Costs																
06	FISH & WILDLIFE FACILITIES	\$84,700	\$25,630	30.26%	\$110,330	0.0%	\$84,700	\$25,630	\$110,330	\$0	\$110,330		\$148,417		\$190,7		
17 17	BEACH REPLENISHMENT (Breach Closure Costs) BEACH REPLENISHMENT (Beachfill Renoutshment)	\$76,200 \$813,279	\$23,058 \$185,578	30.26%	\$99,258 \$798.857	0.0%	\$76,200 \$813,279	\$23,058 \$185,578	\$99,258 \$798,857	\$0 \$0	\$99,258 \$798,857		\$135,903 \$1,008,227	\$41,124	\$177,00 \$1,313,3		
17	BEACH REPLENSHMENT (CPF Renourishment)	\$121,480	\$36,754	30.26%	\$158,213	0.0%	\$121,480	\$38,754	\$158,213	\$0	\$158,213		\$217,713		\$283.5		
17	BEACH REPLENISHMENT (SLC Adaptation)	\$20,089	\$6,079	30.26%	\$26,168	0.0%	\$20,089	\$8,079	\$26,168	\$0	\$28,168	48.3%	\$29,784	\$9,013	\$38,79		
30	E&D and S&A							******									
31	PLANNING, ENGINEERING & DESIGN CONSTRUCTION MANAGEMENT	\$117,490	\$35,552	30.26%	\$153,042 \$75,917	0.0%	\$117,490	\$35,552 \$17,638	\$153,042 \$75,917	\$0	\$153,042 \$75,917	298.8%	\$434,144		\$565,51 \$302,73		
31	RENOURSHMENT COST TOTALS:			30.26%	\$1,421,786	uus	\$1,091,499		\$1,421,786	\$0			\$2,204,598		\$2,871,70		
		CHIEF, (COST EN	IGINEER	ING, Muke	sh Kun	nar										
		PROJECT MANAGER, Frank Verga					ESTIMATED INTO					TAL PROJECT COST:			\$1,725,10		
		CHIEF, I	REAL ES	TATE,													
										ESTIMATED I	RENOURISHM	URISHMENT PROJECT COST:					
						ESTIMATED TOTAL PROJECT COST							COST:		\$4,596,81		


Cost & Schedule Risk Analysis (CSRA) Results

(double-click to open in Adobe)










Schedule

(double-click to open in Adobe)



ATR/Cost Certification

(double-click to open in Adobe)

WALLA WALLA COST ENGINEERING MANDATORY CENTER OF EXPERTISE

COST AGENCY TECHNICAL REVIEW

CERTIFICATION STATEMENT

For Project No. 403357

NAN – Atlantic Coast of Long Island Fire Island Inlet to Montauk Point (FIMP) Long Island, New York

The Fire Island Inlet to Montauk Point (FIMP) General Reevaluation Report (GRR), as presented by New York District, has undergone a successful Cost Agency Technical Review (Cost ATR), performed by the Walla Walla District Cost Engineering Mandatory Center of Expertise (Cost MCX) team. The Cost ATR included study of the project scope, report, cost estimates, schedules, secalation, and risk-based contingencies. This certification signifies the products meet the quality standards as prescribed in FR In10-2-150 Engineering and Design for Civil Works Projects and ER 1110-2-1302 Civil Works Cost Engineering.

As of September 24, 2019, the Cost MCX certifies the estimated total project cost:

FY19 Project First Cost: \$2,942,719,000
Initial First Cost: \$1,520,933,000
Renourishment First Cost: \$1,421,786,000
Fully Funded Amount: \$4,596,815,000

It ramains the responsibility of the District to correctly reflect these cost values within the Final Report and to implement effective project management controls and implementation procedures including risk management through the period of Federal Participation.



FOR: Michael P. Jacobs, PE, CCE Chief, Cost Engineering MCX Walla Walla District

WALLA WALLA COST ENGINEERING MANDATORY CENTER OF EXPERTISE

COST AGENCY TECHNICAL REVIEW

CERTIFICATION STATEMENT

For Project No. 403357

NAN – Fire Island to Montauk Point General Re-Evaluation Report

The Fire Island to Montauk Point General Re-Evaluation Report, as presented by New York District, has undergone a successful Cost Agency Technical Review (Cost ATR), performed by the Walla Walla District Cost Engineering Mandatory Center of Expertise (Cost MCX) team. The Cost ATR included study of the project scope, report, cost estimates, schedules, escalation, and risk-based contingencies. This certification signifies the products meet the quality standards as prescribed in RE 1110-2-150 Engineering and Design for Civil Works Projects and ER 1110-2-1302 Civil Works Cost Engineering.

As of August 23, 2016, the Cost MCX certifies the estimated total project cost of:

| Nitial Project Costs: | \$\frac{\text{Fife Project First Cost}}{\text{\$\$\exitt{\$\$\text{\$\$\text{\$\$\text{\$\$\text{\$\$\text{\$\$\text{\$\$\text{\$\$\text{\$\$\text{\$\$\text{\$\$\text{\$\$\exitt{\$\$\text{\$\$\exitt{\$\$\exitt{\$\$\text{\$\$\exitt{\$\$\text{\$\$\text{\$\$\exitt{\$\$\text{\$\text{\$\$\text{\$\$\text{\$\$\text{\$\$\text{\$\$\text{\$\$\text{\$\$\text{\$\text{\$\$\

It remains the responsibility of the District to correctly reflect these cost values within the Final Report and to implement effective project management controls and implementation procedures including risk management throughout the life of the project.

he project.



Kim C. Callan, PE, CCE, PM Chief, Cost Engineering MCX Walla Walla District